

WELL PLUGGING RECORD

State Of Kansas
State Corporation Commission
130 S. Market, Room 2078
Wichita, KS 67202
Lease Operator: Petroleum Property Services, Inc.
155 N. Market #1000, Wichita, KS 67202
Phone 316-265-3351
Character of Well: OIL

API Number: 15-151-20767 - 00-000
Lease Name: BERRY
Well Number: 1
330 Ft. From S Section Line
990 Ft. From E Section Line
Sec: 32 TWP: 26S RGE: 14W
Operators License No. 31142 PRATT County:
Date Well Completed: 4/81-4-30-81
Plugging Commenced: 6/6/2001
Plugging Completed: 6/11/2001

The plugging proposal was approved on: 6/6/2001
by: STEVE DURRANT

KCC District Agent

Is ACO-1 Filed: NA\* If not, is well log attached? SENT WITH P&A APPLICATION

Table with 4 columns: Producing Formation, Depth to Top, Bottom, T.D. Rows include LECOMPTON and LKC.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Rows include LECOMPTON O&W and LKC O&W.

\* ACO-1 WAS NOT IN COMPANY RECORDS OR KGS RECORDS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or plugs were used, state the character of same and depth place, from \_\_\_ feet to \_\_\_ feet each set.

PLUG BACK WITH SAND 4105-3425, DUMP 5 SX CEMENT 3425-3382, SHOT OFF PIPE AT 2032, PULL PIPE UP TO 1225, PUMP 13 SX GEL APPOX 1225-1180, 50 SX 60/40 POZ, 6% GEL, APPOX 1180-1005. PULL PIPE TO 310, PUMP 50 SX 60/40 POZ, 6% GEL, APPOX 310-135. PULL PIPE TO 40 AND FILL TO SURFACE WITH 10 SX 60/40 POZ, 6% GEL. HOLE STAYED FULL.

Plugging Contractor: QUALITY WELL SERVICE
Address: 415 EAST MAIN, STERLING, KS 67579

License No. 31925

Name of Party Responsible For Plugging Fees: Petroleum Property Services, Inc.

STATE OF: KANSAS COUNTY OF: SEDGWICK, SS.
R.J. Thatcher (Employee of Operator) or (Operator), of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

Signature: [Handwritten Signature]
Address: 3535 American Drive, Colorado Springs, CO 80917

SUBSCRIBED AND SWORN TO before me this 2nd day of July, 2001

ROSANN M. SCHIPPERC
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 9/28/03
My Commission Expires: 9/28/03

[Handwritten Signature: Rosann M Schippers]
Notary Public

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 3 2001

CONSERVATION DIVISION

OR