

WELL PLUGGING RECORD

State Of Kansas
 State Corporation Commission
 130 S. Market, Room 2078
 Wichita, KS 67202
 Lease Operator: Petroleum Property Services, Inc.
 155 N. Market #1000, Wichita, KS 67202
 Phone 316-265-3351
 Character of Well: OIL

API Number: 15-151-20705-00-00-00-00
 Lease Name: McMANNIS
 Well Number: 1
 330 Ft. From S Section Line
 3630 Ft. From E Section Line
 Sec: 33 TWP: 26S RGE: 14W
 Operators License No. 31142 PRATT County: 3-1-80
 Date Well Completed: 3/80
 Plugging Commenced: 6/11/2001
 Plugging Completed: 6/12/2001

The plugging proposal was approved on: 6/11/2001
 by: STEVE DURRANT

KCC District Agent

Is ACO-1 Filed: YES If not, is well log attached?

Producing Formation:	Depth to Top	Bottom	T.D.
TOPEKA	3494	3497	
LKC	3932	3936	4148

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
TOPEKA	O&W	3494	3497	8 5/8	304	0
LKC	O&W	3932	3936	4 1/2	4144	2229

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or plugs were used, state the character of same and depth place, from ___feet to ___feet each set.

SAND BACK FROM 4104 TO 3435, DUMP 4 SX CEMENT W/BAILER 3435-3380. SHOT OFF PIPE AT 2229, PULL PIPE UP TO 950, PUMP 13 SX GEL APPOX 950-900, 50 SX 60/40 POZ, 6% GEL APPOX 900-725. PULL PIPE TO 330 & PUMP 50 SX 60/40 POZ, 6% GEL APPOX 330-155. PULL PIPE TO 40 & FILL WITH 10 SX 60/40 POZ, 6% GEL, TO SURFACE. HOLE STAYED FULL.

Plugging Contractor: QUALITY WELL SERVICE
 Address: 415 EAST MAIN, STERLING, KS 67579

License No. 31925

Name of Party Responsible For Plugging Fees: Petroleum Property Services, Inc.

STATE OF: KANSAS COUNTY OF: SEDGWICK, SS.
R.J. Thatcher (Employee of Operator) or (Operator), of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

Signature: R.J. Thatcher
 Address: 3535 American Drive, Colorado Springs, CO 80917

SUBSCRIBED AND SWORN TO before me this 2nd day of July, 2001

ROSANN M. SCHIPPER
 NOTARY PUBLIC
 STATE OF KANSAS
 My Appt. Exp. 7/28/03
 My Commission Expires: 9/28/03

Rosann M Schippers
 Notary Public

RECEIVED
 KANSAS CORPORATION COMMISSION
 JUL 3 2001
 CONSERVATION DIVISION
 OR