

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pratt

County. Sec. 36 Twp. 26S Rge. 14W (E) (W)

Location as "NE/CNW&SW&" or footage from lines SW SW NW

Lease Owner Sierra Petroleum Co., Inc.

Lease Name McMINNIS Well No. 1

Office Address 420 W. Douglas Ave., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry

Date well completed 8/9/57 19

Application for plugging filed 8/8/57 19

Application for plugging approved 8/8/57 19

Plugging commenced 8/9/57 19

Plugging completed 8/9/57 19

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4600' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	451	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PLUGGING REPORT

Filled hole with heavy mud from 4600' up to 350'. Set plug with 1/3 sack hulls, wood plug and 20 sacks cement through drill pipe. Filled hole with heavy mud up to 35'. Set bridge with 1/3 sack hulls wood plug, 10 sacks cement to cellar 0. Job complet 4:45 a. m. 8/9/57.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sierra Petroleum Co., Inc.

Address Box 232, Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.

G. T. Honaker (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. T. Honaker

(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of August, 19 57.

My commission expires 1-30-61.

Margie Cooper Notary Public
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC. 36 T. 26 R. 14W
BOOK PAGE 35 LINE 11

Sierra Petroleum Co., Inc.

McMANNIS #1

SW SW NW Sec: 36-26S-14W
Pratt County, Kansas

Total Depth: 4600'

Comm: 7/22/57

Comp: 8/9/57

Casing:

8 5/8 @ 451'

Cement:

with 300 sacks

FORMATION	DEPTH
Sand	155
Red bed	450
Red bed, shale & shells	876
Anhydrite	895
Shale & shels	1540
Shale & lime	2205
Lime	2475
Lime & shale	3090
Lime	3138
Lime & shale	3366
Lime	4290
Miss.	4310
Lime (Miss)	4325
Miss.	4362
Kinderhook	4382
Lime & chert	4403
Viola	4462
Lime	4496
Simpson	4538
Lime & shale	4572
Arbuckle	4600

Tops:	FORMATION	DEPTH
Anhydrite		875
Lansing K. C.		3845
Mississippi		4290
Kinderhook		4362
Viola		4403
Simpson		4496
Arbuckle		4572

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

C. D. Hanaker

Subscribed and sworn to before me this 13th day of August, 1957.

Margie Cooper
Notary Public

My commission expires: 1-30-61.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 36 T 26 R 14W
BOOK PAGE 35 LINE 11

AUG 14 1957
CONSE V. DIVISION
Wichita, Kansas