

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Pratt County, Sec. 27S Twp. 26 Rge. 12 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE SE SE

Lease Owner Raymond Oil Company, Inc.

Lease Name MARDIS Well No. 1

Office Address 410 Fourth National Bank Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed September 11 19 62

Application for plugging filed September 11 19 62

Application for plugging approved September 11 19 62

Plugging commenced September 11 19 62

Plugging completed September 11 19 62

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Herman Justus, Nickerson, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4432 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	344'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill hole to 180'. Set plug 1/4 Sx. hulls  
25 Sxs. cement. Fill with mud to 35'.  
Set plug 1/4 Sx. hulls, 10 Sxs. cement.  
2 Sxs. cement in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

OCT. 10 1962  
10-12-62  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Raymond Oil Company, Inc.

Address 410 Fourth National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Wm. M. Raymond (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wm M Raymond

410 Fourth National Bank Building, Wichita (Address)

SUBSCRIBED AND SWORN TO before me this 10th day of October, 19 62

Barbara A. Kennedy  
Notary Public.

My commission expires July 9, 1966

RAYMOND OIL COMPANY, INC.  
 No. 1 MARDIS  
 NE SE SE 27-26S-12W  
 Pratt County, Kansas

ELEVATION: 1881 GL  
 1883 DF  
 1885 KB

Commenced: August 27, 1962  
 Completed: September 11, 1962  
 Contractor: Raymond Drilling Company - Rig #5

Casing Record:  
 8-5/8" @344' w/250 Sx.

Figures Indicate Bottom of Formation

<u>Formation</u>	<u>Depth</u>
Sand	235
Shale and Shells	345
Redbed	750
Shale and Shells	1720
Anhydrite	1644
Lime - Broken	1885
Lime and Shale	3640
Lime	4120
Chert - Lime	4165
Lime	4231
Cherty Lime	4275
Lime	4332
Sand, Chert and Lime	4363
Lime	4432 TD

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 OCT 12 1962  
 10-12-62  
 CONSERVATION DIVISION  
 Wichita, Kansas

TOPS

Herrington	1892
Winfield	1950
Towanda	2020
Fort Riley	2060
Base Florence Flint	2152
Wreford	2186
Council Grove	2231
Cottonwood	2391
Heebner	3477
Toronto	3491
Douglas	3516
Brown Lime	3657
Lansing	3678
Base Kansas City	4018
Conglomerate	4062
Mississippi	4080
Kinderhook	4200
Viola	4225
Simpson Shale	4319
Simpson Sand	4322
Simpson Dolomite	4351
Rotary Total Depth	4432

