

15-151-38772-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

PRATT County. Sec. 27 Twp. 26 Rge. 12W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SW NE
Lease Owner. SANTA-FE PIPE & SUPPLY, INC.
Lease Name. STEAD Well No. 1
Office Address. P. O. BOX 562 - GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) OIL
Date well completed DECEMBER 20 19 63
Application for plugging filed JUNE 16 19 65
Application for plugging approved JUNE 18 19 65
Plugging commenced JUNE 17 19 65
Plugging completed JULY 1 19 65
Reason for abandonment of well or producing formation DEPLETED

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4456 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	375'	NONE
				5 1/2"	4419'	3045'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4419'	-	4300'	-	SAND
4300'	-	4260'	-	5 SACKS CEMENT
4260'	-	300'	-	MUD
300'	-	290'	-	ROCK BRIDGE
290'	-	215'	-	25 SACKS CEMENT
215'	-	40'	-	MUD
40'	-	30'	-	ROCK BRIDGE
30'	-	BASE	-	10 SACKS CEMENT

RECEIVED
STATE CORPORATION COMMISSION

AUG 18 1965

8-18-65

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor SANTA-FE PIPE & SUPPLY, INC.
Address P. O. BOX 562 - GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
T. L. NUTT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

P. O. BOX 562 - GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of AUGUST, 1965

My commission expires July 31, 1966

Mary M. Guesnier
Notary Public.

15-151-30172-0000
 WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas


COPY

Company- NATE APPELMAN
 Farm- Stead No. 1

SEC. 27 T. 26 R. 12W
 SW SW NE

Total Depth. 4485'
 Comm. 12-5-63 Comp. 12-20-63
 Shot or Treated.
 Contractor. Leben Drilling Inc.
 Issued. 4-11-64

County Pratt
 KANSAS



CASING:
 8 5/8" 375' cem w/300 sx.
 5 1/2" 4419' cem w/200 sx.

Elevation. 1911' KB

Production. 104 BOPD / 21% WTR.

Figures Indicate Bottom of Formations.

surface clay & sand	70
sand	195
shale	210
shale & redbed	685
Anhydrite	710
shale & shells	1660
shale	1800
shale & lime	1915
lime & shale	2134
shale & lime	2510
shale	3130
shale & lime	3250
lime & shale	3668
lime	4100
lime & chert	4162
lime & shale	4208
lime	4485 RTD
Total Depth	

TOPS: LOG	
Council Grove (sample)	2262
Cottonwood "	2422
Heebner	3509
Toronto	3516
Douglas	3544
Brown Lime	3683
Lansing	3706
Base Kansas City (sample)	4046
Marmaton (sample)	4049
Mississippi	4118
Viola	4246
Simpson Shale	4308
Simpson Sand	4332
Arbuckle	4412

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 18 1965
 8-18-65
 CONSERVATION DIVISION
 Wichita, Kansas