


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

PRATT County, Sec. 27 Twp. 26 Rge. 12W (E) (W)
Location as "NE/CNW/SW" or footage from lines SW NE NE
Lease Owner SANTA-EE PIPE & SUPPLY, INC.
Lease Name STEAD Well No. 2
Office Address P. O. BOX 562 - GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed APRIL 3 19 64
Application for plugging filed MAY 8 19 65
Application for plugging approved MAY 10 19 65
Plugging commenced JULY 1 19 65
Plugging completed JULY 17 19 65
Reason for abandonment of well or producing formation DRY HOLE



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well MR. A. ELVING
Producing formation Depth to top Bottom Total Depth of Well 4416 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	361'	NONE
				5 1/2"	4399'	3168'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4416' - 4390' - SAND
4390' - 4350' - 5 SACKS CEMENT
4350' - 300' - MUD
300' - 290' - ROCK BRIDGE
290' - 266' - 8 SACKS CEMENT
266' - 250' - MUD
250' - 240' - ROCK BRIDGE
240' - 165' - 25 SACKS CEMENT
165' - 40' - MUD
40' - 30' - ROCK BRIDGE
30' - BASE - 10 SACKS CEMENT

RECEIVED
STATE CORPORATION COMMISSION
AUG 18 1965
8-18-65
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor SANTA-EE PIPE & SUPPLY, INC.
Address P. O. BOX 562 - GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
T. L. NUTT

(Employee or owner) of (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. L. Nutt
P. O. Box 562 - Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of August, 19 65

My commission expires July 31, 1966
Mary W. Guesnier
Notary Public.

15-151-00493-00-01

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company- CONTINENTAL OIL
Farm- Marie G. Stead No. 2

SEC. 27 T. 26 R. 12W
SW NE NE

Total Depth. 4400'
Comm. 3-21-64 Comp. 4-3-64
Shot or Treated.
Contractor. Western Pet.
Issued. 8-15-64

County Pratt
KANSAS



Elevation. 1888 KB

Production. DRY

CASING:

8 5/8" 361' cem w/ 285 sx
5 1/2 4399

Figures indicate Bottom of Formations.

clay & sand	35
shale	85
sand	362
red bed	859
anhydrite	876
shale & shells	1587
lime & shale	2850
shale & lime	3205
lime & shale	3327
lime	4024
lime & shale	4091
chert, lime	4154
lime & chert	4191
chert	4226
lime, chert	4259
shale	4263
shale & sand	4288
sand & shale	4316
chert & shale	4434
sand & shale	4400 RTD
Total Depth	

TOPSL SMP	
Anhydrite	640
Heebner	3476
Toronto	3481
Douglas	3513
Brown lime	3653
Lansing	3672
Base Kansas City	4012
Mississippian	4084
Kinderhook	4176
Viola	4190
Simpson shale	4272
Simpson sand	4295
<i>Arbuckle</i>	4374
Core # 1 4259-4308'	

RECEIVED
STATE CORPORATION COMMISSION

AUG 18 1965
8-18-65
CONSERVATION DIVISION
Wichita, Kansas