

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pratt County. Sec. 27 Twp. 26 Rge. 12 (E) (W) X

Location as "NE/CNW/SW" or footage from lines NE NE SW

Lease Owner Continental Oil Company

Lease Name James R. Cooper Well No. 1

Office Address _____

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 13 1964

Application for plugging filed April 14 1964

Application for plugging approved April 14 1964


Plugging commenced April 14 1964

Plugging completed 5:00 P.M. April 14 1964

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie Elving

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4370' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	367	8-5/8	367	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pushed wooden plug and hulls to 300' with drill pipe. Cemented w/25 sxs. common cement through drill pipe. Filled hole to 40'. Pushed wooden plug and hulls to fluid. Cemented with 10 sxs. cement, 2 sxs. cement in rat hole. Job completed @ 5:00 P.M. April 14, 1964.

RECEIVED
STATE CORPORATION COMMISSION

APR 24 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Western Petroleum Co., Inc.

Address 925 Patton Road, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

F. L. Copeland (employee of owner) or ~~owner~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

State Corp. Comm. File (Signature) F. L. Copeland

925 Patton Road, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of April, 1964

Elaine F. Bentley
Notary Public.

My commission expires 2/11/68

RECEIVED
APR 23 1964

GREAT BEND DISTRICT

DRILLER'S LOG
JAMES R. COOPER #1

COMPANY: CONTINENTAL OIL Co.
 CONTRACTOR: WESTERN PETROLEUM Co., INC.
 COMMENCED: APRIL 4, 1964
 COMPLETED: APRIL 15, 1964
 DESCRIPTION: NE 1/4 SW
 SECTION 27-T26S-R12W
 PRATT COUNTY, KANSAS

ELEVATION: 1903 DF
 1905 KB
 CASING RECORD: 12 JTS, 8-5/8" 8 RD.
 THD. 24# J-55 SEAMLESS PIPE.
 TOTAL DEPTH: 4370'

FORMATION	FROM	TO	REMARKS
CLAY & SAND	0	40	SPUD 12 1/4" HOLE @ 10:30 A.M. 4/4/64 RAN 12 JTS. 8-5/8" 8 RD. THD. 24# J-55 SEAMLESS PIPE. 363.26' OVERALL SET @ 367'. CEMENTED w/255 SXS. COMMON CEMENT, 2% CC. PLUG DOWN 5:30 P.M.
SHALE & SAND	40	70	
SHALE	70	130	
SAND	130	191	
RED BED	191	685	
ANHYDRITE	685	710	
SHALE, SHELLS	710	1345	
SHALE & SHELLS, LIME	1345	1841	
LIME & SHALE	1841	2740	
SHALE & LIME	2740	3178	
LIME & SHALE	3178	3427	
SHALE & LIME	3427	3525	
LIME & SHALE	3525	3700	
LIME	3700	4115	
CHERT	4115	4143	
CHERT & LIME	4143	4192	
LIME & CHERT	4192	4222	
LIME, SHALE, CHERT.	4222	4262	
SHALE & LIME	4262	4275	
CHERT	4275	4296	
CHERT & SHALE	4296	4340	
SAND	4340	4370	
RTD	4370		

RECEIVED
 STATE CORPORATION COMMISSION

APR 24 1964

CONSERVATION DIVISION
 Wichita, Kansas

SAMPLE TOPS

BROWN LIME	3678	-1773
LANSING	3699	-1794
B/KC	4036	-2131
MISSISSIPPIAN	4110	-2205
KINDERHOOK	4247	-2342
VIOLA	4265	-2360
SIMP. SHALE	4313	-2408
SIMP. SAND	4323	-2418
B/SIMP. SAND	4344	-2439

RECEIVED
 APR 28 1964
 TOWN OF BARTON

STATE OF KANSAS)
 COUNTY OF BARTON) SS

I, THE UNDERSIGNED, BEING DULY SWORN ON OATH, STATE THAT THE ABOVE STATEMENT AND LOG ARE TRUE AND A CORRECT RECORD AND LOG OF THE WELL DRILLED AT THE LOCATION ABOVE DESCRIBED.

State Corp. Comm.
 Kansas Geo. Society
 File

WESTERN PETROLEUM CO., INC.

John H. Volosin
 JOHN H. VOLOSIN, VICE-PRESIDENT

SUBSCRIBED AND SWORN TO BEFORE ME THIS 17TH DAY OF APRIL, 1964.

Elaine F. Bentley
 ELAINE F. BENTLEY, NOTARY PUBLIC

MY COMMISSION EXPIRES 2/11/68