

15-151-10598-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittig Building
Wichita, Kansas

WELL PLUGGING RECORD

PRATT County, Sec. 20 Twp. 26S Rge. (E) 12 (W)

Location as "NE/CNW/SW" or footage from lines C SE SW SW

Lease Owner ALADDIN PETROLEUM CORP.

Lease Name HOEME Well No. 2

Office Address 809 PETROLEUM BLDG. WICHITA, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) OIL

Date well completed APRIL 25 1956

Application for plugging filed FEB. 17 1956

Application for plugging approved " 17 1956

Plugging commenced " 19 1956

Plugging completed " 23 1956

Reason for abandonment of well or producing formation NOT PROFITABLE

If a producing well is abandoned, date of last production FEBRUARY 19 56

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well M. A. RIVES

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4306 Feet

Show depth and thickness of all water, oil and gas formations. P.B. 4170

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	793	NONE
				5 1/2	4296	3403

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4170	TO	4115	SAND
4115	TO	4090	5 SAX CEMENT
4090	TO	300	SQUEEZED WITH 50 SAX BY HALLIBURTON
300	TO	285	ROCK BRIDGE
285	TO	225	20 SAX CEMENT
225	TO	30	MUD
30	TO	CELLAR	10 SAX CEMENT

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & S PIPE PULLING CO.

Address ELLINWOOD, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. M. JOHNSON

809 PETROLEUM BLDG. WICHITA, KANSAS (Address)

SUBSCRIBED AND SWORN to before me this 8TH day of MARCH, 1956

My commission expires NOV - 1 - 1959

Jaime English - Notary Public.

PLUGGING
FILE SEC 20 T 26 R 12W
BOOK PAGE 39 LINE 22

MAR 14 5
3-14-56
CONSERVATION DIVISION
Wichita, Kansas

ALADDIN PETROLEUM COMPANY

SE/4 SW/4 SW/4 Sec. 20-26S-12W
Pratt County, Kansas

HOEME # 2

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay & Sand	0	115	
Shale & Shells	115	175	
Red Bed Shale & Shells	175	385	8-5/8" C.S.A. @ 793'.
Red Bed & Shells	385	793	Cemented with 450 sacks.
Anhydrite	793	815	
Shale & Shells	815	1215	
Shale & Shells	1215	1670	
Lime & Shale	1670	1845	
Lime	1845	1955	
Lime & Shale	1955	2095	
Lime	2095	2195	
Brc. Lime	2195	2420	
Shale & Lime	2420	2475	
Lime & Shale	2475	2595	
Shale & Shells	2595	2775	
Shale & Lime	2775	3190	
Lime	3190	3380	
Lime & Shale	3380	3475	
Lime	3475	3560	
Sandy Lime & Shale	3560	3650	
Shale & Lime	3650	3659	
Brown Lime	3659	3684	
K. C. Lime	3684	3690	
Lime	3690	4108	
Lime & Chert	4108	4186	
Lime	4186	4193	
Shale & Sand	4193	4243	
Shale & Lime	4243	4293	5-1/2" C.S.A. @ 4296'.
Lime & Sand	4293	4299	Cemented with 150 sacks.
Total Depth		4299'	

I here by certify the foregoing to be a true and accurate Driller's Log on the formations encountered in the above well.

TRANSIT CORPORATION

By: L. C. Kruse
 L. C. Kruse, Secretary

Subscribed and sworn to before me this 26th day of August, 1952.

3-14-56

Sullivan W. Wright
 Notary Public

My Commission Expires: Oct. 24, 1955

PLUGGING			
FILE	SEC-20	Y-26	R-12W
BOOK	PAGE	LINE	
	39	22	