

15-151-26389-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pratt SEC. 11 TWP. 26S RGE. 12W E/W
Location as in quarters or footage from lines:
NW SE NW

Locate Well
correctly on above
Section Pratt.

Lease Owner Davies & Company, Inc.
Lease Name Helen Hogan #1 Well No. _____
Office Address 4501 E. 31st. Suite 101 Tulsa, Oklahoma 74135
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 12-5-81
Plugging completed 12-9-81
Reason for abandonment of well or producing formation _____
Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation _____ Depth to top _____ bottom T.D. 4131'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	407'	none
				5-1/2"	4130 1/2'	2895'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Made bottom hole plug back with sand to 3740' and ran 5 sacks cement. Shot pipe @2885'
and pulled a total of 74 joints. Squeezed hole with 15 sacks gel, 6 sacks hulls,
10 sacks gel, released plug and displaced with 150 sacks common cement, 2% gel, 3% cc.
Plugging Completed.

RECEIVED
STATE CORPORATION COMMISSION

DEC 14 1981
12-14-81
CONSERVATION DIVISION
Wichita Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of December, 19 81

My Commission expires:



Irene Hoover
Notary Public.

July 5, 1977

DRILLERS LOG

COPY

#1 Hogan
NW SE NW
Sec. 11-26S-12W
Pratt County, Kansas

OPERATOR: Davies & Company, Inc.
CONTRACTOR: B & B Drilling, Inc.
COMMENCED: June 23, 1977
COMPLETED: July 3, 1977

8 5/8" @ 407' w/250 sx

0	1155	Sand, Shale & Redbed
1155	1760	Sand & Shale
1760	2265	Shale
2265	2888	Line & Shale
2888	4131	Lime
4131		RTD

5 1/2" @ 4130 1/2' w/200 sx

We certify that the above and foregoing is a true and correct copy of the log on the #1 Hogan located in Pratt County, Kansas.

B & B DRILLING, INC.


Bill Lahar
 STATE CORPORATION COMMISSION
 RECEIVED
 AUG 30 1981
 CONSERVATION DIVISION
 Wichita, Kansas

Subscribed and sworn to before me this 5th day of July, 1977.

Betty M. Abbott
 Betty M. Abbott-Notary Public

My Commission Expires:

January 22, 1979



177

RECEIVED
 STATE CORPORATION COMMISSION

AUG 31 1981
 8-31-81
 CONSERVATION DIVISION
 Wichita, Kansas