


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Map Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Blitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Pratt County. Sec. 13 Twp. 26S Rge. 11 (E) W (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NW SE  
Lease Owner Vickers Explorations, Ltd.  
Lease Name Jeffers Walker Well No. 1  
Office Address Box 2240 Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed June 19 19 53  
Application for plugging filed June 18 19 53  
Application for plugging approved June 18 19 53  
Plugging commenced June 19 19 53  
Plugging completed June 19 19 53  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives Pratt, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4464 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	401	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole w/ mud to 300'. Set plug; Dump 20 sx cement on plug.

Set plug @ 40'. Dump 10 sx cement on plug.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 14 1953  
CONSERVATION  
WICHITA

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Jayhawk Drilling Co., Inc.  
Address Box 2240 Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
John M. Little (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John M. Little

Box 2240 Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 13 day of July, 1953

My commission expires August 13, 1953.

23-8390-s 6-51-20M Notary Public.

PLUGGING  
FILE SEC 13 T 26 R 11 W  
BOOK PAGE 109 LINE 30

VICKERS EXPLORATIONS, LTD.

Jeffers - Walker Well #1  
NW NW SE Sec. 13-26S-11W  
Pratt County, Kansas

Casing Record  
8 5/8" @ 401' w/ 250 sx

Commenced: May 29, 1953  
Completed: June 19, 1953

Elevation 1803 R. B.  
D. & A.

LOG

Sand	0-135
Shale	135-300
Red Beds	300-401
Shale	401-755
Red Beds, Shale & Shells	755-1080
Salt Shale & Shells	1080-1460
Shale & Lime	1460-1615
Lime	1615-1755
Lime & Shale	1755-1880
Lime, Sand & Shale	1880-2020
Lime & Shale	2020-2850
Shale & Lime	2850-2955
Lime & Shale	2955-3245
Lime	3245-3346
Black Shale	3346-3351
Lime	3351-3375
Black Shale	3375-3381
Lime	3381-3384
Shale	3384-3393
Lime	3393-3401
Shale & Sand	3401-3441
Sand	3441-3478
Shale, Thin Lime Streaks	3478-3549
Lime	3549-3553
Shale	3553-3564
Lime, little Shale	3564-4015
Chert	4015-4056
Lime	4056-4086
Shale	4086-4197
Dolomite	4197-4227
Shale	4227-4252
Chert, Dolomite	4252-4300
Lime	4300-4337
Shale, Some Sand & Dolomite	4337-4416
Dolomite	4416-4464 T.D.*

D.S.T. 3639-3666 open 20 min.  
Weak blow 5 min. Recovered 25' mud.  
I.F.P. F.F.P. 18# B.H.P. 1060# 20 min.  
Still building.

D.S.T. 3769-3791 open 1 hr.  
Good blow. Recovered 720' sw.  
F.P. 50# - 430# B.H.P. 1400# 20 min.

D.S.T. 4018-4060 open 1 hr.  
Fair blow 35 min. Rec. 15' mud.  
Trace oil specks B.H.P. 0#

D.S.T. 4254-4280 open 1 hr.  
Good blow Rec. 120' gas 65' slightly cut  
watery mud.  
F.P. 0# - 40# B.H.P. 260# 15 min. still building.

D.S.T. 4334-4396 open 1 1/2 hr.  
Good blow Rec. 630' S.W. B.H.P. 1250#  
in 30 min.  
Ran Schlumberger.

SAMPLE TOPS:

Heebner	3375
Douglas	3401
Brown Lime	3549
Lansing	3564
Mississippian	4015
Kinderhook Shale	4086
" Dolomite	4197
X.L.N. Viola	4326
Simpson	4337
Arbuckle	4416
*Viola Dolomite	4252

I hereby certify that this Log is true and correct to the best of my knowledge and belief.

THE VICKERS EXPLORATIONS, LTD.

BY James T. Walker

Subscribed and sworn to before me this 1 day of July, 1953.

My Commission expires August 13, 1953.

Allen P. Denton  
Notary Public

**PLUGGING**  
FRIT SEC 13 T & R 11W  
BOOK PAGE 109 LINE 20