

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-22,008-00-00

LEASE NAME Fisher

WELL NUMBER 1-18

1650 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 18 TWP. 26 RGE. 11 (E) or (W)

COUNTY Pratt

Date Well Completed 10-10-90

Plugging Commenced 10-10-90

Plugging Completed 10-10-90

LEASE OPERATOR Deutsch Oil Company

ADDRESS 107 N. Market - Suite 1115 Wichita, KS 67202

PHONE# (316) 267-7551 OPERATORS LICENSE NO. 3180

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-09-90 (date)

by District #1 Mr. Middelton (KCC District Agent's Name),

Is ACO-1 filed? to be filed If not, is well log attached? yes
by operator

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4280'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom Plug: @ 600' w/50 sacks cement thru drill pipe
 Next Plug: @ 290' w/50 " " " " " 15 sacks in Rat Hole
 Top Plug: @ 40' w/10 " " " " " 10 sacks in Mouse Hole
 fill water well

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Duke Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss. OCT 16 1990

John Armbruster (Employee of Operator) or ~~Representative~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John Armbruster
(Address) P.O. Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 12 day of Oct, 1990



Dorothy M Hague
Notary Public

COPY

K C C

DRILLER'S WELL LOG

OCT 16 1990

DATE COMMENCED: October 4, 1990
DATE COMPLETED: October 10, 1990

Deutsch Oil Company
FISHER #1-18
SE NE SW
Sec. 18, T26S, R11W
Pratt County, Ks.

ELEVATION: 1869 K.B.

0 - 263' Surface Soil, Sand, Clay
263 - 600' Shale
600 - 620' Anhydrite
620 - 4057' Shale & Lime
4057 - 4212' Shale, Lime, Chert
4212 - 4280' Chert & Lime
4280' RTD

Surface Pipe: Set new
8-5/8", 20# pipe @262'
w/160 sacks 60/40 pozmix
2% gel 3% cc.

A F F I D A V I T


STATE OF KANSAS
COUNTY OF BARTON) ss

John Armbruster of lawful age does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

John Armbruster

Subscribed and sworn to before me this 12 day of October 1990.

Wesley M. Hague
Notary Public



STA-

OCT 16