

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD
OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

NORTH

0			

Locate well correctly on above
Section Plat

Pratt County, Sec 18 Twp 26 Rge 11 (E) (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines NW NW NW

Lease Owner National Cooperative Refinery Association

Lease Name Stark Well No. 2

Office Address 820 Union National Bank Building, Wichita, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 9-15 1943

Application for plugging filed 5-11 1948

Application for plugging approved 5-15 1948

Plugging commenced 6-19 1948

Plugging completed 6-24 1948

Reason for abandonment of well or producing formation

No Production

If a producing well is abandoned, date of last production 11-15 1947

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Viola Depth to top 4149 Bottom Total Depth of Well 4159 Feet

Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	319	-
				5-1/2"	4149	2501'11"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Rocked hole from 4154 to 4125'. Run 5 sacks cement. Mudded hole to 319'. Run 15 sacks cement. Mudded hole to 20'. Run 10 sacks cement. Completed



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to National Cooperative Refinery Association
Address 820 Union National Bank Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

I, L. A. Quillen (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *L. A. Quillen* L. A. Quillen
820 Union National Bank Building, Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of July, 1948

Mabel Tally

Notary Public.

My commission expires February 11, 1950



PLUGGING
FILE SEC 18 Twp 26 R 11 W
BOOK PAGE 29 USE 24

STARKE NO. 2

(George E. Reeves)

Location: NW/4 NW/4 Section 18-26-11, Pratt County.
Elevation: 1860'
Completed: September 15, 1943.
Casing - Surface: 8-5/8" 32#, Cemented with 175 sacks (319')
Casing - Oil String: 5 1/2" 11#, Cemented with 200 sacks (411,9').
Initial Production: Gas 4,370,000 plus 1,102 barrels of oil. September 8, 1943.
Secondary Production: (Field Test) - 93 barrels of oil. January 4, 1946.
74% water.
Last Production: November 15, 1947. 2 barrels of oil, 95% water.



Geo. E. Reeves

Stark No. 2 C NW 1/4, 18-26-11W.,
Pratt County, Kansas

Commenced: 8/2/43

Rotary Completion: 8/23/43

Cable Tool Completion: 9/15/43

Contractor: Sharon Drilling Company, Inc.

Elevation: 1860'

Rotary Total Depth: 4149'

Total Depth: 4154'

CASING RECORD

8 5/8" 319' Cemented w/175 sacks Cement.
5 1/2" O. D., 4146' Cemented w/200 sacks Cement.

DRILLERS LOG

Surface Dirt	0' - 11'	Broken Lime	2530'
Sand&Clay	40	Shale	2815
Sand	165	Broken Lime	2870
Red Bed	600	Shale & Shells	2975
Red Bed & Shale	1015	Shale	3120
Red Rock	1050	Lime	3150
Shale & Shells	1230	Lime & Shale	3220
Sale & Shale	1380	Lime Soft	3300
Lime	1490	Lime	3394
Shale	1595	Lime & Shale	3520
Lime & Shale	1700	Shale & Sand	3552
Lime & Sand	1730	Shale & Shells	3584
Lime	1890	Shale	3598
Broken Lime	1935	Shale & Lime	3688
Lime	2175	Lime	3921
Shale	2185	Lime & Shale	3994
Lime	2200	Lime & Chert	4004
Shale & Lime Streaks	2299	Chert & Shale	4039
Shale	2430	Shale	4146
Lime	2445	Lime & Chert	4151' = 4149'
Shale	2465	T. D.	4154'

I do hereby certify that to the best of my knowledge and belief the foregoing log is true and correct.

SHARON DRILLING COMPANY, INC.


By D. S. Lutes

State of Kansas)
County of Sedgwick) ss.

Subscribed and sworn to before me a Notary Public in and for the County and State aforesaid this 18 day of September 1943.

My commission expires:
Sept. 16 - 1944

[Signature]
Notary Public



PLUGGING
FILE SEC 18 T 26 R 11W
BOOK PAGE 29 LINE 24