

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County, Sec. 18 Twp. 26S Rge. (E) 11 (W)

Location as "NE/CNW&SW" or footage from lines C W 1/2 NW NE

Lease Owner E. K. Edmiston Drilling Co., Inc.

Lease Name SHRIVER Well No. 1

Office Address 425 First National Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 1-11 1969

Application for plugging filed 1-11 1969

Application for plugging approved 1-11 1969

Plugging commenced 1-11 1969

Plugging completed 7:15 PM 1-11 1969

Reason for abandonment of well or producing formation No oil or gas found in commercial quantities.

If a producing well is abandoned, date of last production -- 19--

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren, Pratt, Kansas

Producing formation None Depth to top Bottom Total Depth of Well 4218 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	370'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud back to 600'. Set plug with 50 sacks cement. Mud back to 300'. Set plug with 25 sacks cement. Mud back to 40'. Set solid bridge with 10 sacks cement, 2 sacks in rat hole. Plug down 7:15 PM 1-11-69.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co., Inc.
Address 1425 Wichita Plaza - Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wilson Rains (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
1425 Wichita Plaza - Wichita, Kansas 67202 (Address)



SUBSCRIBED AND SWORN TO before me this 15 day of January, 1969

Sherry Gish Notary Public.
RECEIVED STATE CORPORATION COMMISSION

JAN 17 1969
CONSERVATION DIVISION
Wichita, Kansas

JAN 16 1969

ROTARY DRILLING LOG

Operator: E. K. Edmiston
Drilling Co., Inc.
SHRIVER #1
C W $\frac{1}{2}$ NW NE 18-26S-11W
Pratt County, Kansas

Contractor: Rains & Williamson
Oil Co., Inc.
Commenced: 1-2-69
Completed: 1-11-69

Casing: 8-5/8" @ 370'/275 sx.
Sunset common cement.

Formations


Clay and Soil	40'
Sand	170'
Red Rock	372'
Shale	465'
Red Bed & Shale	728'
Shale	1010'
Shale and Red Rock	1265'
Shale	1590'
Shale and Lime	1693'
Lime and Shale	2545'
Shale and Lime	3270'
Lime and Shale	3725'
Lime	4218'
Rotary Total Depth (D & A)	4218'

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.


Wilson Rains

Subscribed and sworn to before me, a Notary Public within and for the State of Kansas, County of Sedgwick, this 15 day of January, 1969.


Sherry Gish Notary Public

My Commission Expires:
6-30-71

RECEIVED
STATE CORPORATION COMMISSION
JAN 17 1969
CONSERVATION DIVISION
Wichita, Kansas