

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21-902-00-00

LEASE NAME Schlenz

WELL NUMBER 2 Rabbit

2970 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 19 TWP. 26 RGE. 11 (E or W)

COUNTY, Pratt

Date Well Completed: 10-1-88

Plugging Commenced 10-1-88

Plugging Completed 10-1-88

LEASE OPERATOR National Development Co.

ADDRESS 310 West Central, Suite 117 Wichita, KS 67202

PHONE# (316) 267-1331 OPERATORS LICENSE NO. 5114

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-29-88 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filed? operator to be filed by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4430'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
Bottom Plug: @ 665' w/50 sacks cement thru drill pipe

Next Plug: @ 275' w/40

Top Plug: @ 40' w/10 sacks cement

15 Sacks cement in Rat Hole Fill up water well w/cement
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson (Employee of Operator) or ~~XXXXXXXXXX~~ of above-described well first duly sworn on oath, says: That I have knowledge of the facts, statements, ~~RECEIVED~~ herein contained and the log of the above-described well as filed that the same are ~~STATE CORPORATION COMMISSION~~ and correct, so help me God.

(Signature) Leonard Williamson


(Address) P.O. Box 823 Great Bend, KS 67530

OCT 7 1988

SUBSCRIPTION DIVISION
CONSERVATION DIVISION
Wichita, Kansas

AND SWORN TO before me this 5 day of Oct., 1988

Dorothy M. Hague
Notary Public



DRILLER'S WELL LOG

DATE COMMENCED: September 23, 1988
DATE COMPLETED: October 1, 1988

National Development Co.
SCHLENZ #2 Rabbit
SW SW NW
Sec. 19, T26S, R11W
Pratt County, Ks.

ELEVATION: 1864 K.B.

0	-	648'	Surface Soil, Red Bed,
648	-	667'	Anhydrite
667	-	3423'	Shale & Lime
3423	-	3427'	Shale
3427	-	3616'	Lime & Shale
3616	-	3641'	Shale & Lime
3641	-	3984'	Lime
3984	-	4030'	Shale & Lime
4030	-	4072'	Shale, Lime, Chert, Sand
4072	-	4158'	Lime, Chert
4158	-	4212'	Shale
4214	-	4330'	Chert
4330	-	4407'	Shale & Sand
4407	-	4430'	Dolomite
		4430'	RTD

Surface Pipe: Set used
10-3/4", 32# pipe @260'
w/175 sacks 60/40 pozmix
2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON)ss

Leonard Williamson of lawful age, does swear and state that the facts and statement herein are true and correct to the best of his knowledge.

Leonard Williamson
Leonard Williamson

Signed and sworn to before me this 3rd day of October 1988.

DOROTHY M. HAGUE
NOTARY PUBLIC
STATE OF KANSAS
My Appl. Exp. _____

Dorothy M. Hague
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

OCT 7 1988

CONSERVATION DIVISION
Wichita, Kansas