

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Pratt

County. Sec. 5 Twp. 26S Rge. 14W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NW SW Lot #4

Lease Owner Julius Livingston

Lease Name Boylan-Hager

Well No. A-#1

Office Address 210 Mid-Continent Bldg., Tulsa, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9-22-66 1966

Application for plugging filed 9-22-66 1966

Application for plugging approved 9-22-66 1966

Plugging commenced 9-22-66 1966

Plugging completed 9-22-66 1966

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Herman Justice, Nickerson

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4270 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	388'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pushed Plug to 300', put in 25 sacks cement through drill pipe
Filled with Mud to 40', set plug with 1/2 sack hulls and 10 sacks cement
Put 2 sacks cement in rathole

RECEIVED
STATE CORPORATION COMMISSION

SEP 28 1966

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.

Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.

Leslie Kite (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

Box 486, Great Bend, Kansas 67530

(Address)

SUBSCRIBED AND SWORN to before me this 27th day of September, 1966

Amanda Nichols

Notary Public.

My commission expires April 1, 1967

LEBEN DRILLING

Box ~~488~~ 486

GREAT BEND, KANSAS 67530

DATE September 28, 1966 **RECEIVED**
STATE CORPORATION COMMISSION

to: State Corporation Commission
Conservation Division
500 Insurance Building
212 North Market
Wichita 2, Kansas 67202

SEP 29 1966

CONSERVATION DIVISION
WICHITA, KANSAS

MEMO:

Re-bill this plugging charge and mail directly to: Mr. Julius Livingston
210 Mid-Continent Bldg.
Tulsa, Okla.

As we mailed you yesterday driller's log and all plugging forms, please omit your notation about these forms to Mr. Livingston because he will think Leben Drilling, Inc. has not fulfilled their agreement about this matter.

Incidentally, the the plugging application mailed to you stated that Mr. Livingston was to be charged for this plugging.

Sincerely,

LEBEN DRILLING, INC.

FROM Karen Reynolds

DRILLER'S LOG

COMPANY: Julius Livingston
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: BOYLAN-HAGER A-#1 LOT #4
 LOCATION: C NW SW SEC. 5-26S-14W
 PRATT COUNTY, KANSAS
 COMMENCED: 9-13-66
 COMPLETED: 9-22-66

0	260	Sand
260	388	Blue Shale
388	942	Redbed
942	954	Anhydrite
954	1570	Shale
1570	1900	Shale, Shells
1900	2010	Lime
2010	2020	Shale, Shells
2020	2300	Shale, Lime
2300	2467	Lime, Shale
2467	2725	Shale, Lime
2725	2972	Shale
2972	3610	Shale, Lime
3610	3776	Lime, Shale
3776	4199	Lime
4199	4232	Lime, Shale
4232	4255	Mississippi Chert, Lime
4255	4270	Lime
	<u>4270</u>	<u>RTD - D. & A.</u>

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 28 1966
 CORPORATION COMMISSION
 PRATT COUNTY, KANSAS

Set 8 5/8" used surface casing @ 388' with 365 sacks Common, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the Boylan-Hager A-#1 Well, located C NW SW of Section 5, Township 26 South, Range 14 West, Pratt County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
 COUNTY OF BARTON) SS

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 27th day of September, 1966.

Ulanda Nichols
 Ulanda Nichols

My Commission Expires:
April 1, 1967