


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pratt County. Sec. 5 Twp. 26 S Rge. 14 (X) (W)

Location as "NE/CNW/SW" or footage from lines NW NW SE
Lease Owner Artnell Company / Sierra Petroleum Co., - Contr.
Lease Name GEREKE Well No. 1
Office Address 533 Petroleum Bldg., / 208 Petroleum Bldg., Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) dry
Date well completed 9/28/57 19
Application for plugging filed 9/27/57 19
Application for plugging approved 9/27/57 19
Plugging commenced 9/28/57 19
Plugging completed 9/28/57 19
Reason for abandonment of well or producing formation dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4095 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1350	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

Filled hole with heavy mud from 4095 up to 300'. Set bridge wood plug. 1/3 sks hulls, 20 sks cement through drill pipe. Filled hole up to 35' with heavy mud. Set bridge w/wood plug 1/3 sks hulls and 10 sks cement to cellar 0. Job completed 11:30 a.m. 9/28/57 Mr. Rives

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sierra Petroleum Co., Inc.
Address 208 Petroleum Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
C. T. Honaker (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker
(Address)

SUBSCRIBED AND SWORN to before me this 1st day of October, 19 57

My commission expires 1-30-61. Margie Cooper Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
OCT 2 - 1957
PLUGGING
FILE SEC. 5 T. 26 R. 14W
BOOK PAGE 49 LINE 27

Operator: Artnell Company

Sierra Petroleum Co. - Contr.

GEREKE #1

NW NW SE Sec. 5-26S-14W
Pratt County, Kansas

Total Depth: 4095'

Elev:

Comm: 9/14/57

Comp: 9/28/57

Casing:

Cement:

8 5/8 @ 1350'

with 800 sks cement

FORMATION	DEPTH
Sand & shale	240
Shale	410
Shale, sand & chalk	560
Red bed & shale	710
Red bed & sand	775
Red bed, shale & chalk	908
Anhydrite	930
Shale & shells	965
Shale	970
Anhydrite	1015
Shale	1045
Shale & shells	1345
Shale & chalk	1350
Blue shale	1380
Shale, salt & shale	1840
Shale & lime	1880
Lime	2450
Lime & shale	3372
Lime	3543
Lime & shale	3625
Lime k& shale	3790
Lime	4095

STATE OF KANSAS)
) ss:
 COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

C. P. Honaker

Subscribed and sworn to before me this 1st day of October, 1957.

Margie Cooper
Notary Public

My commission expires: 1-30-61.

RECEIVED
STATE CONSERVATION COMMISSION

OCT 2 - 1957
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 5 T. 26 R. 14W
BOOK PAGE 49 LINE 27