

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-02-3-117

API NUMBER 15-151-20808-00-00

LEASE NAME ABRAMS
 WELL NUMBER #1
 SPOT LOCATION W/2 NW NW
 SEC. 7 TWP. 26S RGE. 14W (E) or
 COUNTY PRATT

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR KELSO CASING PULLING (Purchased from The
Reach Group)
 ADDRESS P.O. BOX 347 CHASE, KS. 67524

Date Well Completed _____
 Plugging Commenced 6-5-84
 Plugging Completed 6-11-84

PHONE # (316) 938-2457 OPERATORS LICENSE NO. 6050

Character of Well OIL
 (Oil, Gas, D&A, SMD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? DODGE CITY, KANSAS

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.O. 4300'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASINO RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	340'	none
				4-1/2"	4300'	2318'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 3590' and 4 sacks cement. Shot casing @2926', 2816', 2713', 2628', 2517', 2412', 2318' and pulled a total of 58 joints of 4-1/2" casing. Plugged surface with 3 hulls, 10 gel, 50 cement, 10 gel, 1 hull, released plug and displaced with 150 cement, 60/40 pos, 2% gel, 3% cc.
 Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
 Address P.O. Box 347 Chase, Kansas 67524

RECEIVED
 STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss.

JUN 13 1984

R., Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

CONSERVATION DIVISION
 Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 12 day of June, 1984



Irene Hoover
 NOTARY PUBLIC

My Commission expires.