


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pratt County. Sec. 7 Twp. 26S Rge. 14W ~~R2W~~
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
1980' FNL & 330' FWL

Lease Owner Dakota Oil & Gas Corporation
Lease Name Abrams Well No. 101
Office Address 1400 Willow Lane-Suite 1000, Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole) 67208
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed May 27, 1978
Application for plugging filed Verbal Application 19__
Application for plugging approved Verbal Approval 19__
Plugging commenced May 27, 1978
Plugging completed May 27, 1978
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production
19__

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 465'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	371'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Filled hole with heavy rotary mud from 4,465 ft. (rotary total depth) to
600 ft. Set plug at 600 ft. and cemented with 50 sacks cement. Filled
hole with heavy rotary mud from 600 ft. to 360 ft. Set plug at 360 ft. and
cemented with 40 sacks cement. Filled hole with heavy rotary mud from
360 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with
12 sacks cement, 3 sacks cement in rat hole.

Plugging operations accomplished utilizing Allied Oil Well cementing
pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Co., Inc.
Box 31, Russell, Kansas 67665

STATE OF Kansas COUNTY OF Sedgwick, ss.

Dean Britting, Agent

(~~EMPLOYEE~~ of owner) ~~XXXXXXXXXXXXXXXXXXXX~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed, and that the same are true and correct. So help me God

(Signature)

Dean Britting

200 N. Main, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of June, 1978

Elsie Willison
Elsie Willison - Notary Public.

My commission expires June 30, 1978



KANSAS DRILLERS LOG

COMPANY Dakota Oil & Gas Corporation

SEC. 7 T. 26S R. 14W
LOC. 1980' FNL & 330' FWL

FARM Abrams

NO. 101

COUNTY Pratt

ROTARY TOTAL DEPTH 4,465'

COMM. May 15, 1978

COMP. May 27, 1978

CONTRACTOR H-30, Inc.

ISSUED June 1, 1978

CASING

10 3/4"

8 5/8" Set at 371' cemented w/275 sxs cement

5 1/2"

4 1/2"

ELEVATION 2,027 K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale and Redbed	925'
Anhydrite	939'
Shale	1,297'
Shale and Lime	2,035'
Shale, Lime and Chert	2,145'
Lime and Shale	2,721'
Lime	2,730'
Lime and Shale	4,081'
Lime	4,138'
Lime and Shale	4,287'
Lime	4,300'
Lime and Shale	4,388'
Lime	4,465'
Rotary Total Depth	4,465'

RECEIVED
STATE CORPORATION COMMISSION

JUN 02 1978

CONSERVATION DIVISION
Wichita, Kansas


I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

Dean Britting
Dean Britting

State of Kansas }
County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 1st day of June, 1978.



Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:

June 30, 1978