

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

PRATT

County. Sec. 8 Twp. 26S Rge. 14W (E) (W)

Location as "NE/CNW%SW%" or footage from lines NE-NE-NW  
Lease Owner Petroleum, Incorporated  
Lease Name GEREKE "E" Well No. 1  
Office Address 311 East Third Street, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 12, 1955  
Application for plugging filed April 18, 1955  
Application for plugging approved April 22, 1955  
Plugging commenced April 22, 1955  
Plugging completed May 12, 1955

Reason for abandonment of well or producing formation No Producing Zones  
If a producing well is abandoned, date of last production ----- 19      
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives, Pratt, Kansas  
Producing formation Kansas City Depth to top 3824' Bottom 4139' Total Depth of Well 4547' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Kansas City	Oil & Water	4,055'	4,061'	8-5/8"	959'	NONE
Kansas City	Oil & Water	4,088'	4,096'	5 1/2"	4,190'	2,154'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from      feet to      feet for each plug set.

(Drilled out to 4,125')

Filled hole with crushed rock from 4,125' to 4,045'. Placed 5 sacks cement from 4,045' to 4,010'. Globe Oilwell Cementing Co. pumped down gel mud filling hole. Pumped down wooden plug set at 340' and filled hole with 100 sacks cement from 340' to base of well cellar.

STATE OF KANSAS  
MAY 12 1955  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Morgan Well Plugging Service (License #43)  
Address 102 West 18th Street, Hutchinson, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
C. J. WILTSE (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. J. Wiltse  
Route 2, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of May, 1955  
Ray E. Anderson  
Notary Public.

My commission expires NOVEMBER 21, 1957

PLUGGING  
FILED SEC 8 T 26 R 14W  
BOOK PAGE 114 LINE 6

# WELL LOG

COMPANY **Petroleum, Inc.**

SEC 8 T. 26 R. 14

FARM **GEREKE 'E'**

NO. 1

LOC. NE NE NW


TOTAL DEPTH **4547'**

COUNTY **Pratt County, Kansas**

COMM. **March 2, 1955**

COMP. **March 27, 1955**

CONTRACTOR **Garvey Drilling Company**



CASING **8-5/8" @ 959' w/525 sax**  
**5 1/2" @ 4190' w/52 sax**

ELEVATION **2018' KB**

PRODUCTION **Lansing**

FIGURES INDICATE BOTTOM OF FORMATIONS

260	Shale & Sand
375	Red Shale
495	Red Bed
550	Sand
775	Red Bed
930	Shale & Shells
956	Shale
965	Anhydrite
950	Shale & Red Bed
985	Anhydrite
1560	Shale & Shells
2380	Lime & Shale
2515	Shale & Shells
3375	Lime & Shale
3490	Lime
3560	Lime & Shale
3705	Lime
3865	Lime & Shale
3980	Lime
3994	Lime & Shale
4102	Lime
4160	Lime & Shale
4252	Lime
4295	Shale
4335	Lime
4365	Lime
4466	Lime & Chert
4485	Sand
4547	Lime
R.T.D.	4547'

Tops:

Heebner: 3641 (-1623)  
 Toronto: 3658 (-1640)  
 Br. Lime: 3794 (-1776)  
 Lansing: 3824 (-1806)  
 Mississippi: 4227 (-2209)  
 Kinderhook: 4246 (-2228)  
 Viola: 4296 (-2278)  
 Arbuckle: 4517 (-2499)

RECEIVED  
 STATE CORPORATION COMMISSION

MAY 24 1955

CONSERVATION DIVISION  
 Wichita, Kansas

State of KANSAS }  
 County of SEDGWICK } ss:

I, Karl E. Becker of Petroleum, Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the GEREKE 'E' #1 well.

*Karl E. Becker*

Subscribed and sworn to before me this 30th day of March 19 55

My Commission Expires: 8-11-58

**PLUGGING**  
 FILE SEC 8 T 26 R 14  
 BOOK PAGE 114 LINE 6

NOTARY PUBLIC