

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-151-21,909-00-00

LEASE NAME Carr "A"

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

1650 Ft. from S Section Line

1650 Ft. from E Section Line

LEASE OPERATOR F & M Oil Co., Inc.

SEC. 9 TWP. 26S RGE. 14 XXXX(W)

434 N. Market

COUNTY Pratt

ADDRESS Suite 250, Wichita, KS 67202

PHONE#(316) 262-2636 OPERATORS LICENSE NO. 5313

Date Well Completed 11-15-88

Character of Well D&A

Plugging Commenced 11-16-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11-16-88

The plugging proposal was approved on 11-16-88 (date)

by State Plugger, Paul Luthi (KCC District Agent's Name).

Is ACO-1 filed? NO If not, Is well log attached? NO

Producing Formation _____ Depth to Top _____ Bottom T.D. 4560'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	415.63'	None

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 9 1988

CONSERVATION DIVISION
 Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Circulate heavy mud in hole. 1st plug from 930' to 730' w/50 sx. 2nd plug from 440' to 240' w/50 sx. 3rd plug from 40' to surface w/10 sx. Rathole-15 sx, water well-5 sx. All cement 60/40 posmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 801 Union Center, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F & M Oil Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 801-Union-Center

Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 6th day of December, 19 88.

Janet A. Stuck
 Notary Public

Commission Expires: 12-29-90

