

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Pratt County, Sec. 9 Twp. 26 Rge. 14 (E) (W)

Location as "NE/CNW&SW" or footage from lines NE/4 NE/4 NE/4

Lease Owner Dunne-Gardner Drilling Co., Inc.

Lease Name Henderson Well No. 1

Office Address 300 Schweiter Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed February 10 19 60

Application for plugging filed February 10 19 60

Application for plugging approved February 10 19 60

Plugging commenced February 10 19 60

Plugging completed February 10 19 60

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel

Producing formation Depth to top Bottom Total Depth of Well 4305 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe		0	380	8-5/8"	1-27-60	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy drilling mud to 240 feet. Set plug, 1/4 sack of hulls and 20 sacks cement. Filled casing with heavy mud to 40', set plug, 1/4 sack hulls and 10 sacks cement. Put 8 sacks cement in rate hole and 2 sacks in bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
FEB 16 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

Address

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Don Gardner

(Employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God DUNNE-GARDNER DRILLING CO., INC.

(Signature) By: Don Gardner 300 Schweiter Bldg, Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of February, 19 60

My commission expires 1-14-64

Doris Nilles
Doris Nilles Notary Public.



14

DRILLER'S LOG

COMPANY: Dunne-Gardner Drilling Co., Inc.
 300 Schweiter Building
 Wichita 2, Kansas

LEASE: C. H. Henderson

WELL: No. 1

LOCATION: NE NE NE Section 9-26S-14W,
 Pratt County, Kansas

CONTRACTOR: Dunne-Gardner Drilling Co., Inc.

DATE COMMENCED: January 26, 1960

DATE COMPLETED: February 10, 1960

TOTAL DEPTH: 4305'

CASING: 8-5/8" surface pipe set @ 380' w/250 sacks

<u>FROM</u>	<u>TO</u>	
0	240	Sand
240	510	Red Bed, Shale and Shells
510	905	Red Bed and Shale
905	930	Anhydrite
930	1155	Shale, Sand and Shells
1155	1915	Shale and Shells
1915	3410	Lime and Shale
3410	3478	Lime
3478	3584	Lime and Shale
3584	3655	Lime
3655	3765	Lime and Shale
3765	4249	Lime
4249	4305	Lime, Shale and Chert
4305		T.D.


RECEIVED
 STATE CORPORATION COMMISSION
 SEP 24 1962
 CONSERVATION DIVISION
 Wichita, Kansas

I certify the above to be true and correct to the best of my knowledge and belief.

DUNNE-GARDNER DRILLING CO., INC.

By 
 Don Gardner

Subscribed and sworn to before me this 21st day of September, 1962.


 Marilyn E. Fox, Notary Public

My Commission Expires:

November 9, 1965