

15-151-10558-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

FORMATION PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

OR

Strike out upper line
when reporting plug-
ging of formations.

Pratt County, Sec. 11 Twp. 26 Rge. 12 (W)

Location as "NE1/4NW1/4SW1/4" or footage from lines G/E 1/2 SE 1/4 NW 1/4

Lease Owner Earl F. Wakefield

Lease Name Ward Well No. B-1

Office Address 307 Union National Bank Building

Character of Well (completed as Oil, Gas or Dry Hole) Abandoned

Date well completed 9/15/49 19

Application for plugging filed 8/15/49 19

Application for plugging approved 8/15/49 19

Plugging commenced 8/2/49 19

Plugging completed 8/11/49 19

Reason for abandonment of well or producing formation non-productive
after so long a time

If a producing well is abandoned, date of last production December 1948

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Depth to top Bottom Total Depth of Well 4323 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		Top	238	8 5/8	238	none
		Top	4125	5 1/2	4125	3545.50

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with mud to 3640, bridged @ 3640 with 5 sax cement, filled with mud to 238, 15 sax cement @ 238, mud to 30, ten sax of cement to top of cellar, started 8/2/49, finished 8/11/49, Universal Casing Pulling Co., Mr. Ragland, Mr. E. F. Wakefield present.

RECEIVED

Conservation Div.

SEP 7 1949

STATE CORPORATION
COMMISSION
KANSAS

(If additional description is necessary, use BACK of this sheet) Earl F. Wakefield

Correspondence regarding this well should be addressed to 307 Union National Bank Bldg.
Address Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgewick, ss.

(employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl F. Wakefield

(Address)

SUBSCRIBED AND SWORN to before me this 6th day of September, 1949

My commission expires 12-23-50

22-2625 2-48-15M

PLUGGING
Notary Public
JAMES T. JONES
106
BOOK PAGE LINE

Farm: Ward B-1
 Lease Owner: Central Petroleum Co. Inc. &
 Earl F. Wakefield
 Contractor: Earl F. Wakefield
 Comm: 8-19-41 Comp: 9-15-41

15-151-10558-2000

Description: G/2 SE 1/4 NW 1/4
 11-26-12W
 County: Pratt

Pipe Record:
 238' 8 5/8"
 4125 5 1/2"

Production: Testing

clay sandy	115	drilled lime	3865
sand	190	lime	3883
shale	234	lime & shale streaks	3952
sandy shale	245	shale & lime	3969
red bed	550	lime & shale	3988
sand	575	lime chirty	4007
red bed	691	shale	4022
anhydrite	697	chirt	4024
shale & shells	730	shale	4025
shale	850	shale & lime	4035
shale & shells	1180	shale & brown lime	4062
shale & salt	1390	lime & shale streaks	4074
lime & shale	1450	chirty brown lime & shale	4093
lime & sandy shale	1610	lime	4097
shale & shells	1635	shale	4108
lime	1895	chirt & lime	4111
lime broken	1965	Top of Viola	4108
sand shale & shells	2036	lime	4116
lime broken	2090	lime cored	4121
shale	2103	lime drilled	4133
sandy lime	2124	lime	4164
broken lime & shale	2193	shale & lime	4174
lime	2281	lime	4190
shale	2285	shale & lime	4199
lime broken	2375	lime & shale	4210
shale	2395	sandy shale	4223
lime broken	2413	shale	4230
lime	2467	shale sandy	4254
lime & shale	2618	shale & sand streaks	4276
shale	2630	shale	4278
lime	2690	shale & iron	4283
shale	2705	lime	4285
lime	2710	cored lime	4292
lime with shale streaks	2810	reamed core hole	
lime	2854	drilled	4296-6
shale	2870	lime	4323
lime, broken	2895	T.D.	4323
lime	2940		
lime with shale streak	2996	Plugged back to 4138'	
shale	3024	Cemented 5" at 4125	
lime broken	3087	Treated with 1000 gallons	
lime	3180		
shale	3193		
lime	3310	State of Kansas	
shale	3318	County of Sedgwick	
lime	3395		
lime soft	3407		
lime	3433		
lime broken	3450		
lime	3478		
lime & sandy shale	3490		
lime sandy	3534		
lime	3560		
shale	3605		
shale & lime shells	3622		
lime	3734		
lime cored	3742		
good sh of oil 3878-82			
good sh of oil 3824-26			
lime	3826		
cored lime	3833		

RECEIVED
 9-13-49
 SEP 13 1949
 STATE CORPORATION
 COMMISSION
 KANSAS

I hereby certify that the above is a true and correct copy of the log of the Ward B-1 Well, located in G/E 1/2 SE 1/4 NW 1/4 11-26-12W, Pratt County, Kansas.

Earl F. Wakefield

Subscribed and sworn to before me this 25th day of Sept, 1941

Edmund D. ...
 Notary Public

My comm. expires 1/15/42

PLUGGING
 FILE REC 11 T 26 42
 10-6-41