


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pratt County. Sec. 11 Twp. 26S Rge. 12W (E) (W)
Location as "NE/CNWxSWx" or footage from lines NW NW SW
Lease Owner Halliburton Oil Prod. Co. & Hellar Drilg. Co., Inc.
Lease Name Stalcup Well No. 1
Office Address 1014 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-23 1960
Application for plugging filed 1-23 1960
Application for plugging approved 1-23 1960
Plugging commenced 1-23 1960
Plugging completed 1-23 1960
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4306 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	342'	8-5/8"	343.14'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 240 ft. Set 1st plug using 1/4 sack hulls 18 sacks cement. Filled hole to 40 feet with mud and set 2nd plug with 1/4 sack hulls and 10 sacks cement on bottom of cellar. Filled rat hole with hulls to bridge.

RECEIVED
STATE CORPORATION COMMISSION
2-23-60
FEB 23 1960

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Hellar Drilling Company, Inc.
Address 1014 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
D. L. Hellar (employee of owner) ~~or (owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. L. Hellar
1014 Union Center
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of February, 19 60

My commission expires March 6, 1961. Martha Lou Bruce Notary Public.



R
WELL LOG

OWNER: Halliburton Oil Prod. Co. & Hellar
 Drilling Company, Inc.
 LEASE: Stalcup #1
 LOCATION: NW NW SW Section 11-26-12W
 Pratt County, Kansas
 COMMENCED: January 9, 1960
 COMPLETED: January 23, 1960
 CASING: 8-5/8" set @ 342' w/300' sacks cement

0 - 216	Sand
216 - 342	Red bed, shale
342 - 1360	Sand, red bed, shale
1360 - 1815	Shale
1815 - 1930	Lime & shale
1930 - 2055	Ft. Riley section
2055 - 2215	Lime, shale
2215 - 2400	Shale, lime
2400 - 2760	Lime, shale
2760 - 2862	Shale w/lime brks.
2862 - 2910	Howard lime
2910 - 3175	Lime & shale
3175 - 3304	Topeka lime
3304 - 3494	Lime & shale
3494 - 3614	Shale & lime
3614 - 3680	Douglas shale
3680 - 3728	Lime
3728 - 3900	Lansing-Kansas City
3900 - 4005	Lime
4005 - 4055	Cherty lime & shale brks.
4055 - 4075	Miss. lime, cherty
4075 - 4103	Cherty lime, shale
4103 - 4145	Kinderhook
4145 - 4193	Viola chert
4193 - 4235	Shale, chert, lime
4235 - 4281	Sandy shale
4281 - 4285	Simpson
4285 - 4306	Arbuckle
4306	Rotary Total Depth D & A

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 23 1960
 2-23-60
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
 COUNTY OS SEDGWICK) SS

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the STALCUP #1, located in the NW NW SW Section 11-26-12W, Pratt County, Kansas, as reflected by the files of the HELLAR DRILLING COMPANY, INC.

HELLAR DRILLING COMPANY, INC.
 BY

D. L. Hellar
 D. L. Hellar, President

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 5th day of February, 1960.

My commission expires March 6, 1961.

Martha Ann Price
 Notary Public