


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Flat

Pratt County, Sec. 11 Twp. 26 Rge. 12 (E) W (W)
Location as "NE/CNW%SW%" or footage from lines. NW NW SW
Lease Owner Hinkle Oil Company
Lease Name Stalcup Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 3-17-65 _____ 19____
Plugging completed: 3-22-65 _____ 19____
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4306 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUL IN	PULLED OUT
				8-5/8"	342'	none
				4-1/2"	3804'	2974'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, sanded to 3750' and dumped 3 sacks of cement @ 3750' with dump bailer. Pulled 4 1/2" casing, bailed hole to 270' and dumped 20 sacks of cement @ 270'. Mudded hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

APR 27 1965

4-27-65

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or ~~XXXXXX~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of March, 19 65

Milton J. Volin

My commission expires May 20, 1968

Notary Public.

WELL LOG

OWNER: Halliburton Oil Prod. Co. & Hellar
 Drilling Company, Inc.
 LEASE: Stalcup #1
 LOCATION: NW NW SW Section 11-26-12W
 Pratt County, Kansas
 COMMENCED: January 9, 1960
 COMPLETED: January 23, 1960
 CASING 8-5/8" set @ 342' w/300 sacks cement

0 - 216	Sand
216 - 342	Red bed, shale
342 - 1360	Sand, red bed, shale
1360 - 1815	Shale
1815 - 1930	Lime & shale
1930 - 2055	Ft. Riley section
2055 - 2215	Lime, shale
2215 - 2400	Shale, lime
2400 - 2760	Lime, shale
2760 - 2862	Shale w/lime brks.
2862 - 2910	Howard lime.
2910 - 3175	Lime & shale
3175 - 3304	Topeka lime
3304 - 3494	Lime & shale
3494 - 3614	Shale & lime
3614 - 3680	Douglas shale
3680 - 3728	Lime
3728 - 3900	Lansing-Kansas City
3900 - 4005	Lime
4005 - 4055	Cherty lime & shale brks.
4055 - 4075	Miss. lime, cherty
4075 - 4103	Cherty lime, shale
4103 - 4145	Kinderhook
4145 - 4193	Viola chert
4193 - 4235	Shale, chert, lime
4235 - 4281	Sandy shale
4281 - 4285	Simpson
4285 - 4306	Arbuckle
4306	Rotary Total Depth
	D & A

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 22 1965
 3-22-65
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
 COUNTY OF SEDGWICK) SS

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the STALCUP #1, located in the NW NW SW Section 11-26-12W, Pratt County, Kansas, as reflected by the files of the HELLAR DRILLING COMPANY, INC.

HELLAR DRILLING COMPANY, INC.
 BY

D. L. Hellar
 D. L. Hellar, President

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 5th day of February, 1960.

My commission expires March 6, 1961.

Henry J. ...
 Notary Public