


15-151-10637-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Pratt County, Sec. 30 Twp. 26 Rge. 12 (E) (W)



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines _____
Lease Owner Great Bend Pipe & Supply Co
Lease Name J.F.A. Sittner Well No. 1
Office Address _____
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 12-3 1958
Plugging completed 12-7 1958
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W.L. Loc Kamp
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	835	None
				4-1/2"	4289	1583.58'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Well Plugged back to 3910' - Top Perforations 3848'
Packed approximately 300' Tubing in hole. Sand to 3500'
Mixed and pumped 5 Sx. Cement. Mud to 40' 10 rock bridge and 10 sx. cement.

RECEIVED
STATE CORPORATION COMMISSION
APR 27 1959
4-27-59
CON DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Co., Inc. License # 399
Address P.O. Box 364 - Great Bend, Kansas.

STATE OF Kansas, COUNTY OF Barton, ss.
Nathan Meltzer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Nathan Meltzer
Box 191, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of April, 1959

Anne Meltzer
Anne Meltzer Notary Public.

My commission expires 3/30/61

PLUGGING
FILE SEC. 30 T. 26 R. 12W
BOOK PAGE 142 LINE 13

15-151-10637-0000

SHELL-J. F. A. SITNER #1
SW SE SE Section 30-26S-12W
Iuka-Carmi Field
Pratt County, Kansas

Casing Record

8 5/8" cem 835 with 450 sax.
4 1/2" cem 4289 with 700 sax; perforated 3848-3854.

- 0 - 180 sand & surface rock
- 200 sand & shells
- 270 sand
- 500 red rock & sand
- 705 red bed & shells
- 738 red bed, shale & shells
- 770 anhydrite
- 835 shale & shells
- 1185 shale
- 1540 shale & salt
- 1715 shale & shells
- 1815 shale
- 2232 lime & shale
- 2355 lime
- 2530 lime & shale
- 2755 shale
- 2914 shale & lime
- 3205 lime & shale
- 3270 lime
- 3375 lime & shale
- 3408 lime
- 3522 lime & shale
- 3602 lime
- 3716 lime & shale
- 3754 lime
- 4060 lime & shale
- 4103 lime & chert
- 4133 chert & lime
- 4148 chert
- 4171 lime
- 4189 lime, chert & pyrite
- 4197 lime & shale
- 4209 sand
- 4218 lime & shale
- 4227 lime & chert
- 4240 shale, sand, chert & pyrite
- 4285 lime & shale
- 4308 dolomite
- 4310 dolomite & quartz sand
- 4316 dolomite, cherty, trace sand T.D.

Formation Tops

- Lansing-Kansas City 3700
- Viola 4118
- Simpson 4165
- Arbuckle 4286

PLUGGING
FILE SEC. 30 T. 26 R. 12W
BOOK PAGE 147 LINE 13

RECEIVED
STATE CORPORATION COMMISSION
NOV 25 1958
11-25-58
CONSERVATION DIVISION
Wichita, Kansas