

15-151-10640-0000


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Pratt County, Sec. 30 Twp. 26 Rge. 12W (E) (W)

Location as "NE/CNW\*SW\*" or footage from lines SW SW SW  
Lease Owner High Plains Production Company  
Lease Name Schwertfeger Well No. 1  
Office Address 300 Insurance Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 3-15-66 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 3-19-66 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well A. Elving  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4333' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sand to 4100 ft. - dump 3 sax cement - pull 1460 ft. 4 1/2" pipe.  
Mud to 300 ft. - 15 ft. rock bridge - dump 4 yds. ready mix cement to surface.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 29 1966

3-27-66

Name of Plugging Contractor Ralph Constock Pipe Pulling Inc  
Address Stafford, KS

STATE OF Kansas, COUNTY OF Stafford, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph Constock  
Stafford, KS  
(Address)

SUBSCRIBED AND SWORN to before me this 22 day of March, 1966

My commission expires Oct-29-1968 Kraig Henry Notary Public.




15-151-10648-0000

SHELL OIL CO., INC.  
 Mollie Schwertfeger No. 1.

SEC. 30 T. 26 R. 12 W  
 SW<sup>c</sup> SW  
 330' f SL 330' f WL SW<sup>1</sup>/<sub>4</sub>

Total Depth. 4333'  
 Comm. 3-21-43 Comp. 4-22-43  
 Shot or Treated. 1000 Gals. Acid  
 Contractor.  
 Issued. 5-29-43

County. Pratt



CASING:  
 8 5/8" 908' Cem.  
 4 1/2" 4292' Cem.

Elevation.

Production. Pot. 3000B.

Figures Indicate Bottom of Formations. DDD 5304 B., No wtr

surface clay	35
shale & sand	125
shale & sand	250
red rock	760
anhydrite	772
shale & shells	909
red rock & shale	942
shale & shells	1345
salt, shale, shells	1730
lime & shale	1912
shale & shells	1992
lime & chert	2047
lime	2057
lime & shale	2198
lime	2285
lime & shale	2932
lime	3065
lime & shale	3179
3179 equals 80 SL Corr.	
lime	4099
lime & chert	4132
chert	4146
shale blk	4152
chert	4174
chert, lime, shale	4187
lime	4191
shale	4199
dolomite	4204
dolomite sdy	4206
shale green	4215
sand	4230
shale green	4248
dolomite	4333
Total Depth.	

RECEIVED  
 STATE CORPORATION COMMISSION

MAR 29 1966  
 3-29-66  
 CONSERVATION DIVISION  
 Wichita, Kansas

Tops:  
 Lansing-K.C. 3717  
 Simpson 4191  
 Arbuckle dolomite 4289

Very good porosity, &  
 oil stain 3821-26  
 good porosity, lgt  
 oil stain 3866-69