

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Knighton Oil Co., Inc.

ADDRESS 710 Petroleum Bldg. Wichita, Ks. 67202

PHONE# (316) 264-7918 OPERATORS LICENSE NO. 5010

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, Is well log attached?

Producing Formation Depth to Top Bottom T.D. 3180'

Show depth and thickness of all water, oil and gas formations.

RECEIVED
 KANSAS CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	425'	none
				4 1/2"	3155'	1768'

JAN 15 1992

CONSERVATION DIVISION
 WICHITA, KS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sanded bottom to 2345' ran 4 sacks cement. Shot pipe @1720'.
Plugged with 3 hulls, 10 gel, 50 cement, 10 gel, 1 hull, 8 5/8" plug, 100 sacks 60/40 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Knighton Oil Co., Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) *R. Darrell Kelso*

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 14 day of January, 19 92

Irene Herzberg
 Notary Public

My Commission Expires:



Marked To Ks. Geol. Survey, 6-23-78
PMK

KANSAS DRILLERS LOG

RECEIVED s. 30 T. 26 R. 12 E
STATE CORPORATION COMMISSION
11-12-91
NOV 12 1991
Loc. NW NW SE
County Pratt

API No. 15 — 151 — 20,396-0000
County Number

Operator

Earl M. Knighton

CONSERVATION DIVISION
Wichita, Kansas

Address 710 Petroleum Building Wichita, Kansas 67202

Well No.

#2

Lease Name

Petrowsky "A"

Footage Location

330 feet from (N)XX line 330 feet from XX (W) line

Principal Contractor

BIG SPRINGS DRILLING, INC.

Geologist

Philip M. Knighton

Spud Date

7-7-77

Total Depth

3180


P.B.T.D.

Date Completed

7-15-77

Oil Purchaser

Getty Oil Company



Locate well correctly

Elev.: Gr. _____

DF _____

KB _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	28#	425'	Regular	250	2% Gel 3% CCL
Production	7 7/8"	4 1/2"	9.5#	3155'	150 Regular 60-40 Pozmix	250	18% Salt-- .75CFR2 12%

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth Interval
			2		3104-08

Size	Setting depth	Packer set at
2 3/8"	3122	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth Interval treated
2000 Gals 28%	3104-08

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.) Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil 8 bbls.	Gas MCF	Water 2 bbls.	Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold) used on lease			Producing Interval (s) 3104-08		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

15-151-20396-0000

Operator

Earl M. Knighton

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Oil

Well No.

#2

Lease Name

Petrowsky "A"

s 30 T 26 R 12 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface Clay, red, shale	0	427		
Red bed and shale	427	1320		
Lime and shale	1320	2303		
Lime and shale	2303	3100		
Lime	3100	3110		
Lime and shale	3110	3146		
Lime	3146	3189		
RTD	3180			

RECEIVED
 STATE CORPORATION COMMISSION
 11-12-91
 NOV 12 1991
 CONSERVATION DIVISION
 WICHITA, KANSAS

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

[Signature]
 Signature
 Petroleum Geologist
 JHE
 June 23, 1978
 Date