


15-151-10638-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Pratt County. Sec. 30 Twp. 26S Rge. 12W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW/SW/SE

Lease Owner Forbes Casing Pulling Co.

Lease Name ~~Box-221, Great Bend, Kansas~~ Sittner Well No. #2

Office Address Box 221, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed Yes 19

Application for plugging approved Yes 19

Plugging commenced 5-6 19 57

Plugging completed 5-9 19 57

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M.A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4287' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				1 1/2"		1,357'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Measured into TD 4287'.  
Plugging started 5-6-57. Finished 5-9-57.  
Plugged off bottom. Perforated from 4240' to 4224'. Squeezed well with 10 sacks cement and 6 sacks mud with 700# pump pressure to 3084'. Pulled pipe out of hole and plugged well with heavy mud to 300' and set permanent rock bridge. Dumped 20 sacks cement. Mud to 35', set rock bridge, and mixed 10 sacks for cap on well.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 11 1957  
5-11-57  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.  
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes  
Box 221, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 10th day of May, 1957.  
Betty S. Edman  
Notary Public.

My commission expires November 8, 1960.

PLUGGING  
FILE SEC 30T 26 R.12W  
BOOK PAGE 10 LINE 12

SHELL-M. F. A. SITTNER #2  
 SW SW SE 30-26S-12W  
 Iuka-Carmi Field  
 Pratt County, Kansas

Casing Record

8-5/8" cem 814 with 400 sax  
 4 1/2" cem 4287 with 800 sax; perforated  
 4224-4240, 3848-3854, 4112-4118 & 4134-4144.

- 0 - 100 surface soil & sand
- 280 sand
- 585 red bed & sand
- 650 red bed & shells
- 750 shale & shells & red bed
- 820 anhydrite, shale & shells
- 825 shale & shells
- 1235 shale
- 1290 shale & shells
- 1765 salt, shale & shells
- 1880 shale
- 2160 lime & shale
- 2235 sandy lime & shale
- 2280 lime
- 2445 lime & shale
- 2637 shale
- 2767 shale & lime streaks
- 3036 shale & lime
- 3165 shale
- 3183 shale & lime
- 3390 lime
- 3480 shale
- 3550 shale & lime
- 3586 lime
- 3714 lime & shale
- 3820 lime
- 3867 sandy lime & cherty streaks
- 4001 lime
- 4037 lime & shale
- 4088 lime
- 4098 chert
- 4117 chert, lime & pyrite
- 4140 chert & lime
- 4168 lime & chert
- 4202 lime
- 4221 shale, sand & chert
- 4246 lime & sand
- 4277 lime
- 4307 lime & shale
- 4317 dolomite TD
- 4169 PB

Formation Tops

Lansing-Kansas City 3697  
 Viola . . . . . 4112  
 Simpson . . . . . 4168  
 Arbuckle . . . . . 4284

Plugs: CIBP 4248 & Calseal to 4243.  
 Drove to 4317.  
 McCullough aluminum BP @ 4270 (leaking).  
 CIBP @ 4262; gravel & cem to 4247.  
 Left guide rubber, cone from retainer  
 & 14" magnesium tail pipe (3 1/2' overall)  
 in hole - top junk 4244.  
 CIBP @ 3925 & Calseal to 3908.  
 Squeeze-cemented 3848-3854 - 58 sax  
 in formation.  
 Drove part of retainer & plugs to 4247.  
 CIBP 4180 & 1 sack cement to 4169 PBTB.

I.P. (Arbuckle) Ind. Cap. 14,340 BO 0 wtr 7-26-43.  
 I.P. (Simpson) 421,700 CFG 10-13-52.  
 I.P. (LKC) 63 BO 31 BW 3-2-53.  
 I.P. (Viola) 1 BO 0 wtr 1-14-57.  
 Last Production: 1-14-57.

RECEIVED  
 STATE CORPORATION COMMISSION

PLUGGING  
 FILE SEC. 30 T. 26 R. 12W  
 BOOK PAGE 10 LINE 12

MAY 1 - 1957  
 5-1-57  
 CONSERVATION DIVISION  
 Wichita, Kansas