

15-151-00448-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pratt County, Sec. 10 Twp. 26S Rge. 12W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NE SE NW

Lease Owner Hinkle Oil Co.

Lease Name Petrowsky Well No. 1

Office Address 1016 Union Center Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed December 13 19 62

Application for plugging filed December 13 19 62

Application for plugging approved December 13 19 62

Plugging commenced December 13 19 62

Plugging completed December 13 19 62

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Herman Justus

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4295 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	367'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 180' 1/4 sx hulls, plug
20 sx cement, mud to 40', 1/4 sx
sx hulls, plug - cement to base
of cellar, 2 sx in rathole.

FILED
STATE CORPORATION COMMISSION
12-20-62

DEC 20 1962
12-20-62

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling

Address Box 173--Russell, Kansas

STATE OF Sedgwick, COUNTY OF Kansas, ss.

George A. Angle

(~~Supervisor~~ owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

George A. Angle
580 Fourth Natl. Bank Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of December 14, 19 62

Daphne V. Head

My commission expires

11-17-66

Notary Public.

15-151-00448-0000

DRILLERS LOG

Petrovsky No. 1

CASING RECORD: 8 5/8" @ 367' w/300 sx cement
 COMPANY: Hinkle Oil Company
 CONTRACTOR: Red Tiger Drilling Co.
 COMMENCED: November 28, 1962
 COMPLETED: December 13, 1962
 DESCRIPTION: C NE SE NW 10-266-12W Pratt Co., Kansas
 ELEVATION: 1877 DF 1880 RB
 TOTAL DEPTH: 4295'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface	0	40	
Sand Clay & Gravel	40	165	
Sand Stringers & Clay	165	180	
Red Bed & Rock	180	368	
Red Bed	368	699	
Gyp	699	704	
Shale Shells & Red Bed	704	825	
Shale & Red Bed	825	985	
Shale & Shells	985	1496	
Salt	1496	1642	
Lime & Shale	1642	3210	
Lime	3210	3347	
Lime & Shale	3347	3690	
Lime	3690	3944	
Lime & Shale	3944	4020	
Lime & Chert	4020	4080	
Shale & Chert	4080	4104	
Shale Chert & Lime	4104	4245	
Shale & Sand	4245	4295	

RECEIVED
 CONSERVATION DIV.
 WICHITA, KANSAS
 DEC 18 1962
 12-18-62

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

George A. Angle

 George A. Angle

Subscribed and sworn to before me this 14th day of December, 1962.

Marjorie V. Head

 Notary Public

My Commission Expires:
11-17-68