

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County, Sec. 10 Twp. 26 Rge. 12 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW SE NW
Lease Owner Hinkle Oil Company
Lease Name Petrowsky Well No. 2
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 1-19-66 _____ 19____
Plugging completed 1-25-66 _____ 19____
Reason for abandonment of well or producing formation Depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4283 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	347'	None
				5-1/2"	4274'	3613'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4283', sanded hole to 4260' and dumped 5 sacks of cement @ 4260' with dump bailer. Pulled 5 1/2" casing, bailed hole to 250', set rock bridge to 240' and dumped 25 sacks of cement @ 240'. Mudded hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
FEB 7 1966
2-7-66
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of January, 19 66

My commission expires May 20, 1968
Milton J. Volin Notary Public.

DRILLER'S LOG

COMPANY: Hinkle Oil Company
 CONTRACTOR: Hellar Drilling Company, Inc.
 LEASE: #2 Petrowsky
 LOCATION: NW SE NW 10-26S-12W, Pratt County, Kansas
 COMMENCED: October 1, 1964
 COMPLETED: October 13, 1964
 CASING: Set 8 5/8" surface casing @ 347'/220 sacks cement

0-190	Sand & shells
190-347	Sand & shale
347-695	Sand & shells
695-712	Anhydrite
712-1100	Red Beds & Anhydrite streaks
1100-1250	Red Beds Anhydrite
1250-1750	Salt & Anhydrite streaks
1750-1885	Cherty lime
1885-1965	Ft. Riley Lime & shale
1965-2137	Cherty Lime
2137-2165	Lime & shale
2165-2455	Shale & Lime
2455-2560	Lime & Shale
2560-2618	Shale & Lime streaks
2618-3580	Lime & shale
3580-3675	Shale & Lime
3675-3685	Lime (K.C.)
3685-3750	K.C. Lime
3750-3860	Lime
3860-3917	K.C. Lime
3917-3954	Lime
3954-4040	Lime & Shale
4040-4089	Lime, Shale & Chert
4089-4114	Lime
4114-4136	Black shale
4136-4227	Lime & Shale
4227-4271	Sand & shale
4271-4283	Dolomite
4283	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 7 1966
 2-7-66
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #2 Petrowsky, located in NW SE NW 10-26S-12W, Pratt County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

By *D. L. Hellar*
 President D. L. Hellar

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 20th day of October, 1964.

Catherine Darcey
 Notary Public - Catherine Darcey

My Commission Expires:
 March 25, 1968.

Latter