


WELL PLUGGING RECORD

Give All Information Completely
The Required Affidavit
File or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pratt County. Sec. 10 Twp. 26S. Rge. 12 (E) (W) X

Location as "NE/CNW/SE/SW" or footage from lines SE SW NE

Lease Owner Halliburton Oil Producing Company

Lease Name Repp Well No. 1

Office Address 520 Cameron Building Oklahoma City 6, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19__

Application for plugging filed 9-23-63 19__

Application for plugging approved _____ 19__

Plugging commenced 9-27-63 19__

Plugging completed 9-29-63 19__

Reason for abandonment of well or producing formation Not economical to try to produce-

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes by Halliburton Oil Producing Company

Name of Conservation Agent who supervised plugging of this well Elving

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well PB 1310 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	3 1/4	None
				5 1/2	None	3029

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Rigged up. Sanded to 3500'. Dumped 5 sacks of cement. Cleaned out cellar.

Working pipe. Shot pipe at 3010'.

Pulling pipe.

Pulling pipe.

Pushed plug to 300'. Build rock bridge. Dumped 5 sacks of cement. Cleaning

threads and put on-pector. Bailing water to 300'. Dumped 15 sacks of cement.

Filled hole and rock bridge with mud. Capped well with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 3 1963

10-3-63
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.

Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

J. O. Forbes

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

J. O. Forbes
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 1 day of October, 19 63

Alvin Baker
Notary Public.

My commission expires May 27, 1964



15-151-19064-0000

DRILLER'S LOG

COMPANY: Halliburton Oil Producing Company, etal
 CONTRACTOR: Hellar Drilling Company, Inc.
 LEASE: #1 Repp
 LOCATION: SE SW NE Section 10-26S-12W
 Pratt County, Kansas
 COMMENCED: August 25, 1963
 COMPLETED: September 7, 1963
 CASING: Set 8 5/8" surface casing @ 343'/200 sackscemen
 Set 5 1/2" casing @ 3798 1/2'/140 sacks cement

0-344	Shale-Red Bed
344-800	Shale-sand-shells
800-1645	Shale & shells
1645-1805	Lime & shale
1805-1965	Ft. Riley Section
1965-2610	Lime & Shale
2610-3070	Shale & Lime
3070-3205	Lime w/shale streaks
3205-3518	Shale & Lime
3518-3698	Lime & Shale
3698-3747	Lime
3747-3780	Lime & Shale
3780-3999	Lime
3999-4059	Lime-chert
4059-4119	Lime
4119-4155	Lime-chert
4155-4207	Chert & Lime
4207-4223	Lime w/chert
4223-4298	Lime
4298-4310	Arbuckle
4310	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 26 1963
 7-26-63
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Repp, located in SE SW NE Section 10-26S-12W, Pratt County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

By *D. L. Hellar*
 President D. L. Hellar

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 24th day of September, 1963.

My Commission Expires:
 March 25, 1964.

Catherine Darcey
 Notary Public - Catherine Darcey