

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 5151-20 780-00-01

LEASE NAME SCHWERTFEGER

WELL NUMBER 1-10

_____ Ft. from S Section Line

_____ Ft. from E Section Line

C NE SW
 SEC. 10 TWP. 26 RGE. 12 (E or W)

COUNTY PRATT

Date Well Completed _____

Plugging Commenced 10-8-91

Plugging Completed 10-11-91

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR PRATT WELL SERVICE, INC.

ADDRESS P O BOX 847 PRATT, KANSAS 67124

PHONE# (316) 672-2531 OPERATORS LICENSE NO. 5893

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on OCTOBER 10, 1991 (date)

by DAN GOODROW (KCC District Agent's Name).

Is ACO-1 filed? YES If not, Is well log attached? _____

Producing Formation MISSISSIPPIAN Depth to Top _____ Bottom _____ T.D. 4355

Show depth and thickness of all water, oil and gas formations. PERFS: 4110-20: 4082-92.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	374	8 5/8	374	0
		0	4359	5 1/2	4359	1816 ft., 41 jts.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

DUMPED SAND TO 50 FT. ABOVE TOP PERFS, DUMPED 5 SX CEMENT ON TOP OF SAND, CUT CASING AND SHOT OFF AT 1816 FT. TOP HOLE PLUG: 300 # HULLS, 10 SX GEL, 50 SX CEMENT, 10 SX GEL, 100# HULLS, 100 SX CEMENT. 10-16-91: TOP OF CEMENT AT 75 FT DOWN FROM TOP. ADDED TO TOP WITH RED MIX. 60-40 POZ AND 6% GEL ON TOP HOLE. 400# MAX. PRESSURE, 100# SIP.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893

Address P O BOX 847 PRATT, KANSAS 67124


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PRATT WELL SERVICE, INC.

STATE OF KANSAS COUNTY OF PRATT, ss.

JUDY BERRY (Employee of ~~XXXXXXXXXXXXXXXXXXXXXXXXXX~~ PLUGGING CONTRACTOR)
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) 90 PWS, Inc.



RECEIVED STATE CORPORATION COMMISSION SUBSCRIBED AND SWORN TO before me this 18th day of October, 19 91

Dorothy M. Ferguson Notary Public

My Commission Expires: February 6, 1993

OCT 22 1991
 10-22-91
 CONSERVATION DIVISION
 Wichita, Kansas