

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH

		X	

Locate well correctly on above
Section Plat

Pratt County, Sec. 3 Twp. 26 Rge. (E) 12 (W)
 Location as "NE/CNW&SW&W" or footage from lines E/2 NW NE
 Lease Owner A. L. Abercrombie, Inc.
 Lease Name Hartsell Well No. 1
 Office Address Great Bend, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Input Well
 Date well completed January 29, 1962
 Application for plugging filed November 14, 1968
 Application for plugging approved November 15, 1968
 Plugging commenced November 26, 1968
 Plugging completed December 5, 1968
 Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren
 Producing formation Viola Depth to top 3608 Bottom 4263 Total Depth of Well 4263 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	256'	0
				7"	4244'	2013'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with sand from 4263' to 3608'. Ran
 5 sacks of cement from 3608' to 3588'.
 Set plug at 255', rock bridge from 255' to 245'.
 Ran 5 sacks of cement, bailed out water and ran
 25 sacks of cement from 245' to 185', mudded
 from 185' to 30'. Ran 15 sacks of cement from
 30' to base of cellar.

Note: This well was a wash down. Old well drilled by Stanolind Oil & Gas Co. in 1941. No well log available.

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 15 1968
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn & Smith Pipe Pulling Co.
 Address Box 156, Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
 A. L. Abercrombie (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. L. Abercrombie
 A. L. Abercrombie
 801 Union Center, Wichita, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 12th day of December, 1968.

My commission expires July 15, 1972

Sue J. Blunck
 Sue J. Blunck, Notary Public.