

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-151-21,804-0000

LEASE NAME Mardis

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 2-35

LEASE OPERATOR Averada Corporation

ADDRESS 105 N. Market, Suite 700 Wichita, Kansas

PHONE#(316) 265-1401 OPERATORS' LICENSE NO. 4864

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? to be filed by operator If not, is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 4311'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom Plug: @ 1180' w/50 sacks 60/40 pozmix 6% gel thru drill pipe

Next Plug: @ 380' w/ 40 sacks " " " " " "

Top Plug: @ 40' w/10sacks " " " " " "

15 sacks cement in Rat Hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Larry Curtis

(Employee of Operator) or ~~Notary Public~~

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECORDED  
STATE CORPORATION COMMISSION  
CONS. DIV. WICHITA

(Signature) Larry Curtis

(Address) Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 20 day of October, 19 86

Deborah M. Hague  
Notary Public

OCT 21 2 1986

10-22-86

My Commission Expires: \_\_\_\_\_

DRILLER'S WELL LOG

DATE COMMENCED: October 8, 1986  
DATE COMPLETED: October 16, 1986

Averada Corporation  
MARDIS 42-35  
SW NW NE  
Sec. 35, T26S, R12W  
Pratt County, Ks.

ELEVATION: 1880 K.B.

0 - 1170' Surface Soil, Sand, Shale, Lime  
1170 - 1187' Anhydrite  
1187 - 3493' Lime & Shale  
3493 - 3517' Lime  
3517 - 3665' Shale  
3665 - 3682' Lime & Shale  
3682 - 4036' Lime  
4036 - 4126' Shale & Lime  
4126 - 4311' Chert & Lime  
4311' RTD

FORMATION DATA

Anhydrite 1170'  
Hsebna 3481'  
Toronto 3493'  
Douglas 3517'  
Br. Lime 3665'  
Lansing K.C. 3682'  
Base K.C. 4036'  
Mississippi 4126'  
RTD 4311'

Surface Pipe: Set new  
8-5/8", 20# pipe @350'  
w/175 sacks 60/00 pozmix  
28 gal 38 cc.

AFFIDAVIT


STATE OF KANSAS  
COUNTY OF BARTON) ss

Larry Curtis of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 20 day of October 1986.

Dorothy M. Hague  
Notary Public



REC'D  
STATE CORPORATION  
CONS. DIV. W-1

OCT 22 1986  
10-22-86