

STATE OF KANSAS
STATE CORPORATION COMMISSION
217 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 151-21578-0000

LEASE NAME Dietz

WELL NUMBER W-3

3730 Ft. from S Section Line

715 Ft. from E Section Line

SEC. 32 TWP. 26 RGE. 12 (R) or (W)

COUNTY Pratt

Date Well Completed 3/1/85

Plugging Commenced 11/15/90

Plugging Completed 11/19/90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Timberline Oil & Gas Corporation

ADDRESS 4447 South Canyon Road, Suite 1
Rapid City, SD 57702

PHONE# (605) 341-3400 OPERATORS LICENSE NO. 9232

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 9, 1990 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Disposal
Producing Formation Arbuckle Depth to Top 4502 Bottom 5100' T.D. 5100'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Arbuckle</u>	<u>Salt water</u>	<u>4502</u>	<u>5100</u>	<u>10 3/4</u>	<u>316</u>	<u>0</u>
				<u>7</u>	<u>4502</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. 100 sx cement plug inside 7" from 3800-3380; perf at 770'. Pump 450 sx out casing. Perf at 380' circulate cement to surface inside 7" and 7"-10 3/4" annulus. Cement from 770' to surface inside and outside 7".

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Bayse Well Service License No. 737

Address P.O. Box 149, Stafford, KS 67578

STATE OF South Dakota COUNTY OF Pennington, ss. NOV 21 1990

Brant C. Grote (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well has been filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 4447 South Canyon Road, Suite 1
Rapid City, SD 57702

SUBSCRIBED AND SWORN TO before me this 19th day of November, 19 90

[Signature]
Notary Public
My Commission Expires: 3/30/96