

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Pratt County. Sec. 32 Twp. 26s Rge. 12w (E) (W)

Location as "NE/CNW/SW" or footage from lines C E₂ NE NE

Lease Owner R W Rine Drilling Company

Lease Name Miskimen Well No. # 1

Office Address % C. Roe, Star Route, Pratt, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed yes 19

Application for plugging approved yes 19


Plugging commenced 4-27-60 19

Plugging completed 5-12-60 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Fred Hampel

Producing formation Depth to top Bottom Total Depth of Well (PB) 4,260 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		3,914'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugging commenced 4-27-60. Plugging completed 5-12-60. Measured into total depth, 4,260'. Plugged off bottom: Dumped 25' of sand and 5 sacks of cement. Pushed plug to bottom. Sanded up hole 30' to 4,180' and dumped 3 sacks of cement on the sand. Worked and shot casing. Loaded hole with water. Circulated and spotted 70 barrels of oil. Shot 5 1/2" casing at 3,914'. Pulled and laid down casing. Plugged hole with mud: Mudded hole up to 300'. Set 10' rock bridge. Dumped 20 sacks of cement. Mudded hole up to 40'. Set 10' rock bridge and capped the well with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 9 1960
6-9-60
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J. O. Forbes, d/h/a Forbes Casing Pulling Company

Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
Box 221, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 13th day of May, 1960

My commission expires December 8th, 1963

Kayann Jenkins
Notary Public.