

15-151-19059-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County. Sec. 32 Twp. 26S Rge. 12 (E) W (W)

Location as "NE/CNW/SW" or footage from lines. 927' EWL & 330' SNL of SW/4

Lease Owner Getty Oil Company

Lease Name V. E. Miskimen

Well No. 1-A

Office Address Box 752, Drumright, Oklahoma 74030

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed May 1944

Application for plugging filed August 27 1968

Application for plugging approved August 27 1968

Plugging commenced August 29 1968

Plugging completed October 22 1968

Reason for abandonment of well or producing formation Recomplete as a Water Supply Well

If a producing well is abandoned, date of last production July 1968

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. J. Martin, Pratt, Kansas

Producing formation Arbuckle Depth to top _____ Bottom _____ Total Depth of Well 4305 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	Oil	4296	4305	8-5/8	465	
				5-1/2	4290	400'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Spotted 50 sacks of regular cement with HA-5. Plugged back to 3976'. Set 8-5/8" cast iron bridge plug at 350' and dumped 2 sacks of calseal on plug, yielding PBTD of 344'. Perforated shallow water sand at 50' - 68' with 2 holes per foot. Acidized perforations with 500 gals. of 15% HCL. Well filled with caving from 344' to 50'. Circulated out cavings. Ran 4" tubing and swabbed well. Again filled with cavings. Circulated clean to 90' and swabbed. Again filled to 50'. Bailed water to 50'. Set 8-5/8" rubber plug at 40'. Filled with sand and rock to 33'. Put in 10 sacks cement plug to 3' of surface. Cut off 8-5/8" casing 3' below ground level. Plugging completed on 10/22/68.

RECEIVED
STATE CORPORATION COMMISSION
OCT 30 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kerr Well Service

Address Pratt, Kansas

STATE OF Oklahoma, COUNTY OF Creek, ss.

W. H. McPhail (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature] Area Supt.

P. O. Box 752, Drumright, Okla. 74030

(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of October, 19 68

P. W. Guillot, Jr.
P. W. Guillot, Jr. Notary Public.

My commission expires 11/23/69

KCC
Truran
Shackelford
File

DRILLERS LOG
V. E. MISKIMEN NO. 1-A

Sand	0 to 50'	
Sand & Shale	190	
Shale & Shells	325	
Shale	380	
Shale & Shells	466	8-5/8" set @ 465' W/200 sx cmt.
Shale	615	
Red Bed	935	
Shale	1010	
Red Bed	1100	
Shale	1305	
Salt	1375	
Shale	1730	
Lime	2280	
Shale	2345	
Shale & Lime	2415	
Lime	2465	
Lime & Shale	2590	
Lime	2635	
Shale & Lime	2850	
Lime	3670	
Shale	3702	
Lime	3725	
Lime K.C.	3820	Top 3692'
Lime	3825	
Lime & Shale	3850	
Lime	3925	
Lime & Shale	3960	
Lime	4030	
Lime & Shale	4066	
Chert & Shale	4140	
Chert	4205	
Shale	4218	
Sandy Lime	4230	
Shale	4285	
Lime Arbuckle	4296	Set 5-1/2" @ 4290 W/250 sx cmt.
Dolomite Lime	4305	T.D. 6/4/44

RECEIVED
STATE CORPORATION COMMISSION
8-28-68
AUG 28 1968
CONSERVATION DIVISION
Wichita, Kansas