


15-151-10704-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Pratt County. Sec. 33 Twp. 26 Rge. 12W (E) (W)  
Location as "NE/CNW/SW" or footage from lines SW/ NW/ NW  
Lease Owner Wayne Kirkman  
Lease Name D. R. Lutes Well No. I  
Office Address P. O. Box 143 Great Bend, Kansas 67530  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 8-10 19 43  
Application for plugging filed 5-14 19 74  
Application for plugging approved 5-15 19 74  
Plugging commenced 5-16 19 74  
Plugging completed 5-29 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Biberstein  
Producing formation Depth to top Bottom Total Depth of Well 4311 1/2 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2,000'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom of hole with rock. Rock from 4311 1/2' to 4200'. Dumped 5 sx of cement. Squeezed well with 2 sx of hulls; 10 sx of aqua gel; 100 sx of cement, filling to the bottom of the cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 3 1974  
6-3-74  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Art Lamb Casing Pulling Co.  
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas COUNTY OF Reno ss.  
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
2809 King St. Hutchinson, Kansas 67501  
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of May 19 74

My commission expires December 31, 1974

[Signature] Notary Public.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bldg., Wichita, Kansas


COPY

15-151-10704-0000

SMITH OIL CO.  
D.R. Lutes No. 1.

SEC. 35 T. 26 R. 12 W  
SW NW  
330' WL 990' PL NW

County. Pratt



Total Depth. 4311 1/2'  
Comm. 6-28-43 Comp. 8-10-43  
Shot or Treated.  
Contractor. Ruso Drlg. Co.  
Issued. 10-2-43

CASING:  
8 5/8" 440' Cem.  
5 1/2" 4288' SIM

Elevation.

Production. Pot. 3000 B.

Figures Indicate Bottom of Formations.

soil & clay	15
sand	355
shale & shells	441
red rock	775
shale & shells	1805
lime	2035
shale	2136
lime	2220
lime brkn	2335
lime	2390
shale	2405
lime	2445
shale	2840
lime	2880
shale	3105
lime sdy	3150
shale	3180
lime	3235
shale & lime	3320
lime	3890
shale & lime	3940
lime	3995
shale	4050
shale & chert	4080
chert	4100
shale & chert	4135
chert	4170
chert & shale	4205
sand & shale	4260
shale & sand	4281
dolomite coarsely xlyn	4306 1/2
no porosity	4283
porous slight stain	4286
sm sh oil	4293
porous & sat. 1000' OIH	
in 2 hrs	4296
2000' OIH in 6 hrs	
2650' OIH in 9 hrs	4298
slight sat.	4301 1/2
no por. or sat.	4306 1/2
dolomite xlyn, slightly	
porous & stained	4311 1/2
Total Depth.	

2000 Gals. Acid 8-2-43  
4000 Gals. Acid 8-11-43

Tops: Lansing	3681
Viola	4114
Simpson Shale	4176
Simpson Dolomite	4191
Simpson Sand	4205
Arbuckle SIM	4283

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 14 1974  
5-14-74  
CONSERVATION DIVISION  
Wichita, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 17 1974  
CONSERVATION DIVISION  
Wichita, Kansas