


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pratt County. Sec. 33 Twp. 26 Rge. 12 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C W/2 NW NW
Lease Owner W. L. Kirkman, Inc.
Lease Name Miskimen #2 Well No. _____
Office Address Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Flat

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 1/19/79 _____ 19____
Plugging completed 2/8/79 _____ 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
depleted

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Owens
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3230
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	395	none
				4 1/2"	3216	2429'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 3095', ran 4 sacks cement. Loaded hole, shot pipe at 2432', pulled 68 joints. Pumped 5 sacks hulls, 25 sacks gel, plug and 125 sacks 50-50, 2% gel and 3% cc.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
FEB 16 1979
2-16-79
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of Feb., 19 79

MARGARET MELCHER
Statewide
My Appt. Exp. Feb. 15, 1983

Margaret Melcher
Notary Public.

My commission expires _____

JUL 20 1978

No. 15-151-20,524-0000

KANSAS DRILLERS LOG

COMPANY W. L. Kirkman, Inc.

FARM Miskimen

NO. 2

REVIEW
WLK
KCE

SEC. 33 T. 26S R. 12W
LOC. C-W/2 NW NW

COUNTY Pratt

ROTARY TOTAL DEPTH 3,230'
COMM. June 26, 1978
CONTRACTOR H-30, Inc.
ISSUED July 19, 1978

COMP. July 2, 1978

CASING

10 3/4"
8 5/8" Set at 395' cemented w/300sxs cement
5 1/2"
4 1/2" Set at 3,217' cemented w/150 sxs cement

ELEVATION 1,915 K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Shale	398'
Shale	1,700'
Lime and Shale	3,230'
Rotary Total Depth	3,230'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

Dean Britting
Dean Britting

State of Kansas }
County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 19th day of July, 1978.

Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:
June 30, 1982

RECEIVED
STATE CORPORATION COMMISSION
DEC - 8 1978
12-8-78
CONSERVATION DIVISION
Wichita, Kansas