

STATE OF KANSAS
STATE CORPORATION COMMISSION
260 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21,874-0000

LEASE NAME Mardis

WELL NUMBER 1

2970 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 34 TWP. 26 RGE. 12 ~~W~~ (W)

COUNTY Pratt

Date Well Completed 1-20-88

Plugging Commenced 1-20-88

Plugging Completed 1-20-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Timberline Oil & Gas Corporation

ADDRESS 105 E. 8th St., Pratt, KS 67124

PHONE# (316) 672-9476 OPERATORS LICENSE NO. 9232

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-15-88 (date)

by Paul Luthi (KCC District Agent's Name).

Is ACO-1 filed? will be by operator if not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4180

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set

Plug #1 set @ 680' with 75 sacks cement through drill pipe

Plug #2 set @ 290' with 50 sacks cement through drill pipe

Plug #3 set @ 40' with 10 sacks cement; 15 sacks in rat hole; fill up water well

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Company, Inc. License No. 5929

Address PO Box 823, Great Bend, KS 67530

STATE OF KANSAS COUNTY OF BARTON, ss.

LEONARD WILLIAMSON


(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leonard Williamson

(Address) PO Box 823, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 27 day of January, 19 88

Dorothy M. Hague
Notary Public
STATE CORPORATION COMMISSION



JAN 29 1988
1-29-88
CONSERVATION DIVISION
Wichita, Kansas

15-151-21874-0000

DRILLER'S WELL LOG

DATE COMMENCED: January 12, 1988
DATE COMPLETED: January 20, 1988

Timberline Oil & Gas Corp.
Mardis #1
SE SE NE
Sec. 34, T26S, R12W
Pratt County, KS

0 - 657' Surface soil, Sand
657 - 681' Anhydrite
681 - 3042' Shale, Lime
3042 - 3493' Lime, Shale
3493 - 3498' Shale
3498 - 3528' Lime
3528 - 4114' Shale, Lime
4114 - 4180' Chert, Lime
4180' RTD

ELEVATION: 1881 K.B.

Formation Data:
Anhydrite 657 - 681'
Indian Cave 2666'
Howard 3042'
Topeka 3149'
Heebner 3493'
Douglas 3528'
Br. Lime 3670'
Mississippi 4114'
RTD 4180'

Surface Pipe: Set new
8-5/8" @ 259' with 175
sacks 60/40 pozmix, 2%
gel, 3% c.c.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

LEONARD WILLIAMSON of lawful age, does swear and state that the facts
and statements herein are true and correct to the best of his knowledge.

Leonard Williamson
Leonard Williamson

SUBSCRIBED AND SWORN to before me this 27 day of January, 1988.

Dorothy M Hague
Notary Public



RECEIVED
STATE CORPORATION COMMISSION

JAN 29 1988
1-29-88
CONSERVATION DIVISION
Wichita, Kansas