

TATE OF KANSAS
TATE CORPORATION COMMISSION
30 S. Market, Room 2070
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-02-3-117

API NUMBER 15-151-22046-0000

LEASE NAME Mardis

WELL NUMBER 5-34

330 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 34 TWP. 26 SRGE. 12W (E) or (W)

COUNTY Pratt

Date Well Completed _____

Plugging Commenced 12-27-00

Plugging Completed 12-28-00

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR VESS OIL CORPORATION
ADDRESS 8100 E. 22nd. St. North #300 Wichita, Ks. 67226

PHONE (316) 682-1537 OPERATORS LICENSE NO. 5030

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)
by Steve Pfeifer (KCC District Agent's Name)

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 4315'

Show depth and thickness of all water, oil and gas formations.

RECEIVED
KANSAS CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10-3/4"	296'	None
				4-1/2"	4312'	2340'

JAN 23 2001
1-23-01

CONSERVATION DIVISION

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug was used, state the character of same and depth placed, from _____ feet to _____ feet each, etc. Plugged off bottom with sand to 4110' and 4 sks. cement. Shot pipe @2700', 2500' and 2340'; pulled up to 700', pumped 20 sks. gel and 50 sks. cement, pulled up to 300', pumped 75 sks. cement, pulled to 40' and circulated 20 sks. cement. 60/40 pos. 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact
statements, and matters herein contained and the log of the above-described well as filed in
the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 22nd. day of January, 2001

[Signature]
Notary Public

My Commission Expires:



Form CP
Revised 05-