

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 209 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-151-22, 072-00-01
 LEASE NAME Henrichs Twin

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1
975 Ft. from S Section Line

4950 Ft. from E Section Line
S-NW-SW-SW

SEC. 34 TWP. 26 RGE. 12 (W)

COUNTY Pratt

LEASE OPERATOR Humman Corporation

ADDRESS 200 West Douglas Wichita, Ks.

PHONE # (316) 263-8521 OPERATORS LICENSE NO. 5050

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed _____

Plugging Commenced 1-23-95

Plugging Completed 1-24-95

The plugging proposal was approved on 1-6-1995 (date)

by Steve Durant (Steve Pfeifer on loc.) (KCC District Agent's Name).

Is ACO-1 filled? yes. If not, is well-log attached? _____

Producing Formation Permian PBD: 4130 Bottom T.D. 4440

Show depth and thickness of all water, oil and gas formations.
Perfs: 4080-86 3928-33 3969-76

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	335	10 3/4	335	0
		0	983	8 5/8	983	0
		0	4170	5 1/2	4170	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
See back of form.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service Inc. License No. 5893


Address PO Box 847 Pratt, Ks. 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Humman Corp.

STATE OF Kansas COUNTY OF Pratt

Judy Berry (Judy Berry) (Employee of Pratt Well Service Inc. or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Judy Berry

(Address) PO PWS, Inc.

SUBSCRIBED AND SWORN TO before me this 6th day of February, 19 95

Walter M. Tugsten Notary Public

My Commission Expires February 6, 1997

January 23, 1995

To location rigged up, rigged for tubing, ran 16 joints of tubing, tagged a tight spot, could not go past tight place. Pulled 16 joints of tubing, ran back 16 joints and 4 7/8" bit, could not get the bit to go through tight spot. Pulled out of the hole. Allied circulated through casing and around back side of casing with 70 bbls of water. Closed well in for day.

January 24, 1995

To location, Allied Wireline tagged cement at 160' from surface. Ran tubing, went through soft cement. Pulled tubing, ran back with 6 joints of tubing, pumped 30 sacks cement down well. Pulled tubing, removed surface head. Ran back 2 joints 1" tubing on backside. Cemented backside with 4 sacks of cement. Laid tubing down, rigged down, moved off.