

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

R 15W NORTH

	•		
	13		

Locate well correctly on above  
Section Plat

Pratt County. Sec. 13 Twp. 26 Rge. 15 (E) W (W)  
 Location as "NE/CNW/SW" or footage from lines NE/4 NE/4 NW/4  
 Lease Owner Deep Rock Oil Corporation  
 Lease Name L. A. Lutes Well No. 1  
 Office Address Box 1051, Tulsa, Oklahoma  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
 Date well completed April 22 19 54  
 Application for plugging filed April 26, 19 54  
 Application for plugging approved April 22 19 54  
 Plugging commenced April 22 19 54  
 Plugging completed April 22 19 54  
 Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes, approval received from M. A. Rives

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4640 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	429	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with heavy mud from TD to 300'. Set wood plug and mixed and dumped in 25 sacks cement to 260'. Filled with heavy mud to 20' and set wood plug. Mixed and dumped in 10 sacks cement to top of pipe and into cellar. Welded steel cap on top of pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R. W. Rine Drilling Company  
 Address 320 Central Building, Wichita, Kansas

STATE OF \_\_\_\_\_, COUNTY OF \_\_\_\_\_, SS.  
 \_\_\_\_\_ (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
701 Petroleum Building, Wichita, Kansas  
 (Address)

SUBSCRIBED AND SWORN TO before me this 5<sup>th</sup> day of May, 19 54

My commission expires 2/13/56

24-7368-6 3-53-20M

**PLUGGING**  
 FILE SEC 13 T 26 R 15W  
 BOOK 29 LINE 19

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 MAY 6 - 1954  
 CONSERVATION DIVISION  
 Wichita, Kansas

NE NE NW  
SECTION 13-26S-15W  
PRATT COUNTY, KANSAS

LUTES WELL NO. 1

CONTRACTOR: THE R. W. RINE DRILLING COMPANY

STARTED: APRIL 7, 1954

FINISHED: APRIL 22, 1954

LOG

SURFACE SAND	0- 40	
SURFACE SAND, CLAY, SHALE & SHELLS	40- 440	10-3/4" csg. @ 429' w/400 sx.
SAND; CLAY, GYP & SHALE	440- 975	
ANHYDRITE	975- 995	
RED BED, SHALE & SHELLS	995-1505	
SHALE & SHELLS	1505-2005	SYFO @ 1500' - 1°
SHALE & LIME	2005-2125	SYFO @ 2000' - 1°
SHALE AND SHELLS	2125-2300	
LIME & SHALE	2300-2550	SYFO @ 2500' - 1°
SHALE, LIME & SHELLS	2550-2743	
LIME & SHALE	2743-3460	SYFO @ 3000' - 1 1/2°
LIME	3460-3550	SYFO @ 3500' - 1°
LIME & SHALE	3550-3606	
LIME	3606-3703	
LIME & SHALE	3703-3820	
LIME	3820-3880	
LIME & SHALE	3880-3913	
LIME	3913-4130	SYFO @ 4000' - 1°
LIME & SHALE	4130-4255	
LIME	4255-4301	
LIME & CHERT	4301-4328	
LIME & SHALE	4328-4335	
SHALE	4335-4360	
LIME & SHALE	4360-4405	
LIME	4405-4424	
LIME & SHALE	4424-4464	
LIME	4464-4478	
LIME & SHALE	4478-4520	
LIME	4524-4560	
LIME & SHALE	4560-4595	
SHALE, SAND & LIME	4590-4630	
LIME & SHALE	4630-4640	


TOTAL DEPTH - D & A

STATE OF KANSAS )  
COUNTY OF SEDGWICK)

I, R. M. GREEN, DO HEREBY CERTIFY THAT THE ABOVE IS A TRUE AND ACCURATE LOG OF THE LUTES WELL NO. 1, LOCATED IN THE NE NE NW, SEC. 13-26S-15W, PRATT COUNTY, KANSAS.

  
ASSISTANT SECRETARY

SUBSCRIBED TO AND SWORN BEFORE ME THIS 28TH DAY OF APRIL, 1954.

  
NOTARY PUBLIC

MY COMMISSION EXPIRES: 7-31-57

**PLUGGING**  
FILE SEC 13 T 26R 15W  
BOOK PAGE 29 LINE 19

IVE