

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

PRATT County. Sec. 13 Twp. 26S Rge. 15 (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE SE

Lease Owner R. W. RINE DRILLING COMPANY

Lease Name LEONARD Well No. 1

Office Address 320 CENTRAL BUILDING, WICHITA, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed JANUARY 9, 1953 19

Application for plugging filed JANUARY 9, 1953 - TELEPHONE 19

Application for plugging approved JANUARY 9, 1953 - TELEPHONE 19

Plugging commenced JANUARY 9, 1953 19

Plugging completed JANUARY 9, 1953 19

Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production NONE 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well M. A. RIVES, PRATT, KANSAS

Producing formation NONE Depth to top - Bottom - Total Depth of Well 4652 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE	SURFACE SAND & RED BED	0	790'	8-5/8"	12-23-52	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

HEAVY MUD FROM 4652' TO 300', WOODEN PLUG AND 20 SACKS OF CEMENT @ 300'.

HEAVY MUD TO 30'. WOODEN PLUG WITH 10 SACKS TO CELLAR.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R. W. RINE DRILLING COMPANY

Address 320 CENTRAL BUILDING, WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

E. H. SLOYER (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. H. Sloyer

320 CENTRAL BUILDING, WICHITA, KANSAS


(Address)

SUBSCRIBED AND SWORN TO before me this 13TH day of JANUARY, 19 53

Leona V Pederson

Notary Public.

My commission expires APRIL 20, 1955.



LEONARD #1

SE-SE-SE  
SEC. 13-26s-15w  
PRATT COUNTY, KANSAS

CONTRACTOR: THE R. W. RINE DRILLING COMPANY  
STARTED: 12-20-52 FINISHED: 1-9-53

LOG

SURFACE SAND	0	300
RED BED	300	971
ANHYDRITE	971	997
SHALE	997	1200
PLUG & CEMENT	744	846
SHALE & SAND	1200	1253
SHALE - SHELLS	1253	1930
LIME	1930	2390
LIME - SHALE	2390	2550
LIME	2550	2662
LIME (BROKEN)	2662	2820
LIME - SHALE	2820	3070
LIME (LITTLE SAND & SHALE)	3070	3200
LIME - SHALE	3200	3455
LIME	3455	3825
LIME & SHALE	3825	3885
LIME	3885	4065
LIME & SHALE	4065	4087
LIME	4087	4363
LIME - SHALE	4363	4462
LIME	4462	4497
CHERTY LIME	4497	4525
LIME	4525	4555
SHALE & SAND	4555	4581
LIME & SHALE	4581	4627
LIME	4627	4652

SYFO @ 1000'

SYFO @ 1500'

SYFO @ 2000' -  $\frac{10}{20}$

SYFO @ 2500' -  $\frac{10}{20}$

SYFO @ 4000' - 1°

TD - D & A  
PLUGGED @ 300' w/20 SX  
AND @ 30' w/10 SX

I, R. M. GREEN, DO HEREBY CERTIFY THAT THE ABOVE IS A TRUE AND ACCURATE LOG OF THE LEONARD WELL No. 1, LOCATED SE-SE-SE SEC. 13-26s-15w, PRATT COUNTY, KANSAS.

R. M. Green  
ASSISTANT SECRETARY

SUBSCRIBED TO AND SWORN BEFORE ME THIS 15<sup>th</sup> DAY OF JANUARY, 1953/

Louisa U. Pederson  
NOTARY PUBLIC

MY COMMISSION EXPIRES APRIL 20, 1955.

**PLUGGING**  
FILE SEC 13 T 26 R 15-3  
BOOK PAGE 72 LINE 1

STATE OF KANSAS  
DEPARTMENT OF REVENUE  
DIVISION OF OIL AND GAS  
PRATT, KANSAS