


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Pratt County, Sec. 12 Twp. 26S Rge. (E) 15 (W)
Location as "NE/CNWxSWx" or footage from lines C/SW NW
Lease Owner United States Hydrocarbon Company
Lease Name Kearns Well No. 1
Office Address 815 Union National Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 21 19 66
Application for plugging filed April 21 19 66
Application for plugging approved April 21 19 66
Plugging commenced April 21 19 66
Plugging completed April 21 19 66
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman, Holyrood, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3862 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	305'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole as follows: Plugged at 295' with 25 sacks of cement and mud to 40; plugged with 1/2 sack of hulls and 10 sacks of cement. Also ran 2 sacks of cement in the rat hole and 2 sacks of cement in the mouse hole. Job completed at 3:00 P. M. April 21, 1966.

RECEIVED
STATE CORPORATION COMMISSION

APR 26 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling, Inc.
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Charles W. Steincamp (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp
Charles W. Steincamp, President
P. O. Box 355, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of April, 19 66

My commission expires December 14, 1969

Elaine H. Taylor
Elaine H. Taylor Notary Public.

D R I L L E R S L O G

#1 Kearns

CASING RECORD: Ran 297.68' of used 8-5/8" surface casing.	COMPANY: United States Hydrocarbon Company	DESCRIPTION: C/SW NW Section 12-26S-15W Pratt Co., Kansas
TOTAL DEPTH: 3862'	CONTRACTOR: Strata Drilling, Inc.	ELEVATION: 2029'KB
	COMMENCED: April 16, 1966	
	COMPLETED: April 21, 1966	

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	250	Ran 297.68' of used 8-5/8" surface casing; set and cemented at 305' with 325 sacks of regular cement, 2% gel and 3% calcium chloride. Plug down at 11:00 A. M. April 17, 1966.
Shale & Clay	250	315	
Shale & Red Bed	315	979	
Anhydrite	979	990	
Shale	990	1034	
Shale, Shells & Lime Streaks	1034	1415	
Shale, Shells & Lime	1415	2015	
Shale & Lime	2015	2190	
Lime & Shale	2190	2760	
Shale & Lime	2760	3020	
Lime & Shale	3020	3800	
Lime	3800	3862	

Total Depth 3862'

RECEIVED
STATE CORPORATION COMMISSION

APR 26 1966

CONSERVATION DIVISION
Wichita, Kansas

D. & A.

Plugged hole as follows: Plugged at 295' with 25 sacks of cement and mud to 40'; plugged with 1/2 sacks of hulls and 10 sacks of cement. Also ran 2 sacks of cement in the rat hole and 2 sacks of cement in the mouse hole. Job completed at 3:00 P. M. April 21, 1966.

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
Charles W. Steincamp, President

Subscribed and sworn to before me this 22nd day of April, 1966.

Elaine H. Taylor
Elaine H. Taylor, Notary Public

My Commission Expires:

December 14, 1969

T I M E L O G

RECEIVED
STATE CORPORATION COMMISSION

APR 26 1966

CONSERVATION DIVISION
Wichita, Kansas

United States Hydrocarbon Company
#1 Kearns
C/SW NW
Section 12-26S-15W
Pratt County, Kansas
Contractor: Strata Drilling, Inc.

DEPTH		MINUTES	REMARKS
FROM	TO		
3500	3510	1-2-2-2- $\frac{1}{2}$ / $1\frac{1}{2}$ -1-1-1-1	
	3520	2-1-2-3-4/4-5-6-5-5	
	3530	3-3-3-5-3/3-5-5-3-5	Conn @ 3521' 4 min.
	3540	3-3-3-3-3/3-3-3-3-2	
	3550	1-2-3-2-2/5-5-3-2-2	
	3560	1-2-3-1-1/1-1-1-1-1	Conn @ 3553' 7 min.
	3570	1-2-2-2-2/1-1-2-2-2	
	3580	2-1-2-1-2/1-2-3-2-3	
	3590	4-3-3-2-2/2-2-2-3-3	Conn @ 3584' 4 min.
	3600	3-2-1-2-2/3-1-1-2-1	
3600	3610	1-1-1-2-1/1-1-2-1-2	
	3620	2-2-2-2-2/2-2-1-1-2	
	3630	1-2-2-1-2/2-2-2-3-2	
	3640	1-1-1-1-1/ $\frac{1}{2}$ - $\frac{1}{2}$ -1-1-1	
	3650	2-2-2-2-2/1-1-1-1-1	Conn @ 3647' 5 min.
	3660	1-1-1-1-1/1-2-2-3-2	
	3670	2-2-3-3-3/3-4-4-3-3	
	3680	2-2-3-5-5/4-5-4-4-5	Conn @ 3679' 5 min.
	3690	3-2-2-2-1/1-5-7-6-3	
	3700	2-2-2-2-4/6-5-2-2-2	
3700	3710	2-3-4-3-4/4-5-4-4-2	Conn @ 3709' 5 min.
	3720	2-3-4-4-4/3-4-5-2-2	
	3730	2-2-2-2-2/2-2-2-2-2	
	3740	1-1-2-2-1/2-2-2-2-2	Conn @ 3740' 3 min.
	3750	2-2-1-2-2/2-2-2-1-2	
	3760	2-2-2-2-2/2-2-2-2-2	
	3770	2-3-2-2-2/2-2-2-3-2	
	3780	2-2-2-2-2/2-2-2-2-1	
	3790	2-2-2-2-1/2-2-2-2-2	
	3800	2-2-1-1-2/2-2-2-2-2	
3800	3810	2-2-2-2-2/2-3-2-2-3	Conn & Ck Rig @ 3802' 8 min.
	3820	2-3-2-2-2/2-3-2-3-2	
	3830	2-2-2-2-3/2-2-3-6-8	
	3840	7-5-2-3-3/2-3-3-3-2	Conn @ 3833' 6 min.
	3850	3-3-3-4-3/3-4-3-4-4	Mix mud from 3807' to 3829'
	3860	4-4-4-4-4/7-9-8-7-6	
	3862	6-6	

ROTARY TOTAL DEPTH 3862'