

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21,221 ⁰⁰⁻⁰⁰

LEASE NAME Curtis "A"

WELL NUMBER 1

SPOT LOCATION C-SE-NW-SE

SEC. 8 TWP. 26 RGE. 15 (E) or (W) (W)

COUNTY Pratt

Date Well Completed 1-8-82

Plugging Commenced 11-5-1985

Plugging Completed 11-8-1985

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR R.J. Patrick Operating

ADDRESS 326 N. Lincoln, Liberal, Ks. 67901

PHONE # (316) 624-8483 OPERATORS LICENSE NO. 6528

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Ks.

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation kindernook Depth to top 4358 bottom 4370 T.D. 4474

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8"	445	0'
Production				4 1/2"	4474	3000'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pumped 2 sks. hulls & 20 sks. cement to 4250' Pressured to 750 lbs. Pumped 50 sks. cement 1100' to 950' - Displaced w/mud to 500' Pumped 50 sks. cement 500' to 350' Displaced w/mud to 40' Put bridge & 10 sks. cement 40' to 0' cut off 8 5/8" 3' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Pulling Ser. License No. 6497
Address P.O. Box F, Sublette, Ks. 67877

STATE OF KANSAS COUNTY OF HASKELL, ss.

I. Edgar J. Eves (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION

(Signature) I. Edgar J. Eves

(Address) Box F, Sublette, Ks. 67877

NOV 15 1985

CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 8th day of Nov., 1985

Sandra L. Eves
Notary Public

My Commission expires: 12-6-88

