


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pratt County, Sec. 6 Twp. 26S Rge. 15W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
100' NE of 3350' FSL, 660' FWL in NW $\frac{1}{4}$
Lease Owner Beren Corporation
Lease Name Southwestern College #1 Well No. 1
Office Address 970 Fourth Financial Center, Wichita, Ks 67202
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

Dry Hole
Date Well completed June 17, 1979 19
Application for plugging filed June 17, 1979 19
Application for plugging approved June 17, 1979 19
Plugging commenced 2:30 PM, June 17, 1979 19
Plugging completed 3:30 PM, June 17, 1979 19
Reason for abandonment of well or producing formation
Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4480'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	420'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud.
Spot 50 sacks 50/50 Pozmix with 2% gel
at 420', solid bridge at 40' with 1/2 sack hulls.
Howco plug, 12 sacks to surface. 3 sacks in rathole.

JUN 28 1979

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. A. Wuellner
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of June, 1979



Charles M. Hall
Charles M. Hall, Notary Public.

commission expires _____

STERLING DRILLING COMPANY

P. O. Box 129

Sterling, Kansas 67579

WELL LOG - - - - - SOUTHWESTERN COLLEGE #1

Located: 100' NE of 3350' FSL, 660' FWL in NW/4, Section
6-26S-15W, Pratt County, Kansas

OWNER: Beren Corporation

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: June 7, 1979

COMPLETED: June 17, 1979

TOTAL DEPTH: 4480'

LOG

CASING RECORD

0 - 130 Sand and Clay
130 - 423 Sand - Shale
423 - 1015 Shale, Bed Bed
1015 - 1885 Shale
1885 - 2260 Shale and Lime
2260 - 2520 Lime
2520 - 2940 Lime and Shale
2940 - 3660 Lime
3660 - 3890 Lime and Shale
3890 - 4480 Lime

Ran 10 joints 8 5/8" casing, 408' set
at 420' K.B. with 200 sacks Howco Lite
and 100 sacks 60/40 Pozmix with 3% cc.
Plug down at 9:45 PM, 6-7-79, by Howco.

Plugged.

RECEIVED
STATE CORPORATION COMMISSION

JUN 23 1979

CONSERVATION DIVISION
LAWRENCE, KANSAS