


STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Pratt County. Sec. 5 Twp. 26S Rge. (E) 15 (W) 15  
Location as "NE/CNW/SW" or footage from lines 1850' FNL, 880' FEL  
Lease Owner Sunray Mid-Continent Oil Company  
Lease Name Neelly Well No. 1  
Office Address Box 788, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed February 9 19 57  
Application for plugging filed February 11 19 57  
Application for plugging approved February 12 19 57  
Plugging commenced February 18 19 57  
Plugging completed February 25 19 57  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4690 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	295'	none
				5 1/2	4164'	2932'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with sand to 4340', ran 5 sacks cement. Pulled casing to 1800' and circulated hole with jell mud. Pulled casing, mudded hole to 295', set 10' rock bridge, ran 20 sacks cement. Mudded hole to 35', set 10' rock bridge, ran 10 sacks cement to base of cellar. Plugging completed.

Well log attached.

**RECEIVED**  
STATE CORPORATION COMMISSION  
FEB 23 1957  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor West Supply Company  
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
N. E. Montgomery (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) N. E. Montgomery  
Box 788, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of February, 19 57

[Signature]  
Notary Public.

My commission expires December 24, 1960

PLUGGING  
FILE SEC 5 T. 26 R. 15W  
BOOK PAGE 140 LINE 121

Sunray Mid-Continent Oil Company  
Tulsa, Oklahoma

Tulsa, Oklahoma  
February 4, 1957

CONTRACTOR: Stickle Drilling Company  
Drilling Commenced: January 8, 1957  
Drilling Completed: January 30, 1957

G. Neelly #1 - Lots  
1 & 2 - Sec. 5-26S-15W,  
Pratt County, Kansas.

DRILLERS LOG

Depth Figures Indicate Base of Formation

Sand & Shale	40	Lime	4119
Surface Soil	85	Lime & Shale Streaks	4165
Sand	220	Lime	4205
Shale	305	Lime & Shale	4225
Shale, Red Bed, & Sand	682	Lime, Chert & Shale	4270
Red Bed, & Sand	875	Lime	4336
Shale & Shells	1120	Lime, Chert & Shale	4384
Anhydrite	1155	Lime	4394
Shale & Shells	1840	Lime, Shale, & Chert	4415
Shale & Lime	1995	Chert & Shale	4450
Lime & Shale	2105	Chert Lime	4496
Lime	2225	Chert & Shale	4505
Lime & Shale	2330	Lime, Shale, & Chert	4545
Lime & Shale Streaks	2405	Lime, & Chert	4565
Lime & Shale	2920	Lime & Shale	4595
Shale & Lime	3020	Lime & Shale & Sand	4611
Shale & Lime Streaks	3185	Lime	4622
Lime & Shale	3250	Shale	4659
Shale & Lime	3525	Arbuckle Dolomite	4668
Lime & Shale	3910	Arbuckle	4687
Lime	4005	Lime	4690 TD
Lime & Shale	4036		

I, Frank E. Stickle, hereby certify the above to be a true and complete Driller's Log of Sunray Mid-Continent Oil Company's G. Neelly #1 - Lot 1 & 2 of Section 5-26S-15W, Pratt County, Kansas.

Frank E. Stickle  
Frank E. Stickle

Lillian T. Bonham  
Notary Public

February 13, 1960

My Commission Expires

RECEIVED  
STATE CORPORATION COMMISSION

FEB 23 1957

PLUGGING CONSERVATION DIVISION  
Vichita, Kansas  
FILE SEC 5 T 26 R 15W  
BOOK PAGE 140 LINE 12