


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Pratt County, Sec. 29 Twp. 26 S Rge. 12 W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW NW NW
Lease Owner Bishop Oil Company
Lease Name Petrowsky Well No. 1
Office Address 808 Brown Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed December 21 1944
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced February 22 1954
Plugging completed February 26 1954
Reason for abandonment of well or producing formation
No longer produces in commercial quantities.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Merle Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4303 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8- 5/8"	357'	None
				5- 1/2"	4298'	3233'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Original total depth was 4303'. A plug was set at 3950' and casing perforated from 3740' to 3748'. Filled hole with sand from 3950' to 3740' and ran 5 sacks of cement. Filled hole with mud to 300', set a 10' rock bridge, and ran 20 sacks of cement at 290'. Mudded hole to 40', set a 10' rock bridge, and ran 10 sacks of cement on top. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Jeff C. Lyle (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Jeff C. Lyle*
(Address) _____

SUBSCRIBED AND SWORN TO before me this 10th day of March, 19 54

William M. Krause
Notary Public.

My commission expires May 25, 1957

24-7368-5 3-53-20M

PLUGGING
FILE SEC 29 T 26 R 12W
BOOK PAGE 10 LINE 22

3-11-54
MARCH 12 1954
CONSERVATION DIVISION
Wichita, Kansas

15-151-60006-0000

Bishop Oil Company
San Francisco, California

Petrowsky Well No. 1

SW/4 NW/4 NW/4
Section 29-26S-12W
Pratt County, Kansas

Contractor: The R. W. Rine Drilling Company

Commenced: November 13, 1944

Completed: December 21, 1944

	<u>LOG</u>	
Sand, Shale, & Gravel	0- 225	
Sticky Shale	225-245	
Sand	245 - 258	
Red Bed	258- 745	8 5/8" casing cemented @ 357'
Anhydrite	745- 775	
Shale & Shells	775-2045	
Lime & Sandy Lime	2045-2265	
Lime & Shale	2265-2795	
Shale	2795-2900	
Shale & Lime	2900-3817	
Lime	3817-4065	
Lime & Chert	4065-4069	
Lime	4069-4113	
Lime & Chert	4113-4177	
Hard Sand & Shale	4177-4187	
Lime & Sand	4187-4232	
Sand & Shale	4232-4256	
Shale & Lime	4256-4275	
Lime	4275-4280	5 1/2" casing cemented @ 4298'
Shale & Sand	4280-4303	Total Depth 4303'

State of Kansas)
County of Barton) ss

I, Clyde W. Goddard, do hereby certify that the above is a true and complete log of the Petrowsky Well No. 1, located in the SW/4 of the NW/4 of the NW/4, Section 29, Township 26S, Range 12W, Pratt County, Kansas.

Clyde W. Goddard

Sworn to and subscribed before me this 27th day of December

Helen S. Williams

My commission expires December 6, 1948.

3-9-54

PLUGGING
PRATT CO. SEC 29-T26-R12W
BOOK PAGE 10 LINE 22