

15-151-19853-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County, Sec. 29 Twp. 26 Rge. 12W (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE $\frac{1}{4}$ NW $\frac{1}{4}$ NW $\frac{1}{4}$

Lease Owner Bishop Oil Company

Lease Name Petrowsky Well No. 2

Office Address 808 Brown Bldg.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 1, 19 51

Application for plugging filed November 29, 19 51

Application for plugging approved 19


Plugging commenced November 1, 19 51

Plugging completed November 1, 19 51

Reason for abandonment of well or producing formation Unable to establish circulation below surface pipe.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well G.D. Stough

Producing formation Depth to top Bottom Total Depth of Well 1338 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Gravel				8 5/8"	456'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole was losing circulation at approximately 700 feet. Placed gunny sacks at 700 feet. Pumped wooden plug to top of sacks. Filled hole with mud to bottom of surface pipe. Squeezed 20 sacks cement through drill pipe from 453' to 392'. Filled hole, with mud to 64'. Placed wooden plug at 64'. Filled hole with 20 sacks cement from 61' to surface.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to D.I. Lawless
Address Bishop Oil Company, 808 Brown Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgewick, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Donald J. Lawless

(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of December, 1951

My commission expires 3/27/54

23-5091-S 6-50-10M

PLUGGING
FILE SEC-29-T 26 R 29
BOOK PAGE 121 LINE 16

12-4-51
DEC - 4 1951
CONSERVATION DIVISION
Wichita, Kansas

Notary Public.

BISHOP OIL COMPANY

Petrowsky # 2

Section 29-26S012W
Pratt County, Kans.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS:</u>
Clay	0	70	
Sand	70	90	
Clay & Shells	90	275	
Red Bed	275	360	
Red Bed & Shells	360	456	8-5/8" C.S.A. @ 456' Cemented with 300 sacks cement.
Red Bed	456	640	
Shale & Shells	640	770	
Lime	770	850	
Shale & Shells	850	1234	
Shale	1234	1520	
Shale & Lime	1520	1725	
Broken Lime	1725	1760	
Total Depth		1760'	

I hereby certify the foregoing to be a true and accurate Driller's log of the formations encountered in the above well.

TRANSIT CORPORATION

By: L. J. Kruse
L. J. Kruse, Ass't Secy.

Subscribed and sworn to before me this 4th day of December, 1951.

William Wright
Notary Public

My Commission Expires: 10-24-1955

PLUGGING
FILE SEC 29T YC R 12W
CHECK PAGE 12 LINE 16

RECEIVED
STATE OF KANSAS
DEC - 7 1951
CONSERVATION SERVICE
Wichita, Kansas